IN BUSINESS SINCE 2005

Hyperline
CABLING SYSTEMS

CM-1U-ML

- 19" Cable Manager with Metal Rings, 1U (ring dimensions: 55 x 44.5 mm (2.17" x 1.75")

Width	19 "(482.6 mm)
Height	1U (44 mm)
The size of the rings	55 x 44.5 mm (2.17" x 1.75")
Number of rings	5
Material panel	Sheet steel 1.4 mm
Material Rings	SPCC Metal

CM-2U-ML

- 19" Cable Manager with Metal Rings, 2U (ring dimensions: 55 x 89 mm (2.17" x 3.5")

Width	19 "(482.6 mm)
Height	2U (88 mm)
The size of the rings	55 x 89 mm (2.17" x 3.5")
Number of rings	5
Material panel	Sheet steel 1.4 mm
Material Rings	SPCC Metal

CM-1U-ML-COV

• 19" Cable Manager with Metal Rings and Cover, 1U (ring dimensions: 45 x 44.5 mm (1.77" x 1.75")

Width	19 "(482.6 mm)
Height	1U (44 mm)
The size of the rings	45 x 44.5 mm (1.77" x 1.75")
Number of rings	21
Material panel	Sheet steel 1.4 mm
Material Rings	SPCC Metal
Cover material	SPCC Metal

CM-2U-ML-COV

• 19" Cable Manager with Metal Rings and Cover, 2U (ring dimensions: 45 x 89 mm (1.77" x 3.5")

Width	19 "(482.6 mm)
Height	2U (88 mm)
The size of the rings	45 x 89 mm (1.77" x 3.5")
Number of rings	21
Material panel	Sheet steel 1.4 mm
Material Rings	SPCC Metal
Cover material	SPCC Metal

CM-ML-REAR

- Rear Cable Manager 482.6 x 78 mm (19" x 3.1")

ORDERING

Part Number	Description
CM-1U-ML	Cable organizer with metal rings, 19 ", 1U
CM-2U-ML	Cable organizer with metal rings, 19 ", 2U
CM-1U-ML-COV	Cable organizer with metal rings and cover, 19 ", 1U
CM-2U-ML-COV	Cable organizer with metal rings and cover, 19 ", 2U
CM-ML-REAR	Rear Cable Manager 482.6 x 78 mm