

Horizontal sidewall sprinklers

Project information

Job name:	Location:
Engineer:	Date submitted:
Contractor:	Submitted by:
Manufacturer's representative:	Approved by:

Technical data

Temp/pressure ratings	73 °F (23 °C) at 160 psi (11 bar) 180 °F (82 °C) at 100 psi (6.9 bar) 200 °F (93 °C) at 80 psi (5.5 bar)
Prop 65 label required?	Yes



Part name	Part no.	Weight per UOM [lbs/UOM]
LF Recessed Horizontal Sidewall Sprinkler, 155F, 4.2 K-factor, White	LF74300HW	0.15
LF Recessed Horizontal Sidewall Sprinkler, 175F, 4.2 K-factor, White	LF74301HW	0.15
LF Flat Concealed Horizontal Sidewall Sprinkler, 165F, 4.0 K-factor	LF74000HS	0.15

Installation

Related applications

-	AquaSAFE™ Fire Safety Systems
---	-------------------------------

Footnotes

Contact information

-	Uponor Inc. 5925 148th Street West Apple Valley, MN 55124 T 800.321.4739 F 952.891.2008	Uponor Ltd. 6510 Kennedy Road Mississauga, ON L5T 2X4 T 888.594.7726 F 800.638.9517
---	---	---