



LIQUIFIED PETROLEUM GAS

shop.hillmangroup.ca



HILLMAN™

**INDUSTRIAL, COMMERCIAL
& RESIDENTIAL
RECREATIONAL & OUTDOOR
BULK STORAGE
TRANSPORT & DELIVERY**



HILLMAN™

For over 60 years, the Dominion brand has been recognized as an industry leading distributor offering a large array of products to serve industrial and LPG industries, automotive aftermarkets, OEM, Plumbing and HVAC wholesalers.

Our five strategically situated warehouses in Vancouver, Edmonton, Winnipeg, Toronto and Montreal are conveniently located to provide courteous service to all of our customers.

Dominion has a broad range of fittings in black malleable, brass, composite, steel and stainless steel. Included in our core product offering is various types of copper and aluminum tubing, tube working tools, clamps and a variety of accessories.

Hoses that range from Thermoplastic to general purpose to flexible gas piping (TracPipe) round out our product offering. Dominion produces custom CSA type I, II, III LPG hose assemblies and D.O.T approved hose assemblies with hundreds of different configurations to suit your specific and unique applications. In addition to the products that we offer, our value added services include sourcing of non-standard products.

Our greatest strength is our employees. We have experienced technical sales and customer service representatives at each of our locations. For our complete line of Propane and Natural Gas products and accessories, please contact any one of our locations. We also offer a broad range of hardware, fasteners and automotive products under our Hillman, Paulin and PAPCO family of brands.

The items listed in our catalogue are a representation of the products available and stocked in our distribution network. Our availability may not represent all sizes available or certain applications required. Please contact your local Hillman customer service or sales representative for additional product inquiries. Our knowledgeable staff will provide you with information and solutions that are both cost effective and reliable.

OFFER OF SALE

All sales and all contracts or agreements made by us are contingent upon strikes, fires, accidents, or other causes beyond our control. All quotations are made for immediate acceptance, and prices are subject to change without notice. Orders for special goods are not subject to cancellation except by written permission and upon the agreement to reimburse us for work already performed. On all orders for special goods, we reserve the right to ship ten percent over or under the quantities specified. No claims for shortage or overcharge will be allowed unless made within ten days after receipt of goods. To avoid mistakes in ordering we ask that you kindly use our catalogue part numbers.

WARRANTY

Limitation of remedy: seller's liability arising from or in any way connected with the items sold or this contract shall be limited exclusively to repair or replacement of the items sold, or refund of the purchase price paid by the buyer, at seller's sole option.

In no event shall seller be liable for any incidental, consequential or special damages of any kind or nature whatsoever, including but not limited to lost profits arising from or in any way connected with this agreement or items sold herein, whether alleged to arise from breach of contract, express or implied warranty, or in tort, including without limitation, negligence, failure to warn or strict liability.

FISHER™
REGULATORS & VALVES

TracPipe **CounterStrike**
Flexible Gas Piping by OmegaFlex.

MEC **MARSHAL EXCELSIOR**
innovation made simple
MARSHALL EXCELSIOR

THE ORIGINAL **Mr. Heater**
HEATSTAR
by **ENERCO**

Dormont
APPLIANCE CONNECTORS

Kam
PRODUCTS LIMITED
COATED COPPER TUBING

BURNABY
MANUFACTURING LTD.

SUPER
EGO

flagro
INDUSTRIES LIMITED

Thermoid®
POLAR-FLEX DELIVERY HOSES

FLAME
ENGINEERING, INC.
Red Dragon Torch

Product Index

ACME COUPLINGS, ADAPTORS & ACCESSORIES

ACME Couplings & Adaptors.....	19-20
ACME Caps & Accessories	21
Ring & Chain Assemblies	21
Spanner Wrench.....	21
Serviceman's Replacement Kit.....	22
Hose Couplings - Clamp Style.....	22
Quick Acting Toggler Valves	22

BALL & NEEDLE VALVES	38
---------------------------------------	-----------

BBQ BOXES	83
------------------------	-----------

BREAKAWAY COUPLINGS	31
----------------------------------	-----------

FITTINGS

SAE Flare	41-44
Pipe	45-48
Welding.....	49
Inverted Flare	50
POL	51-52
Fittings - Black Iron & 3000#	53-67

FLEXIBLE GAS PIPING (TRAC-PIPE)	33-35
--	--------------

GAS CONNECTORS

Residential.....	36
Safety Shield Yellow Coated.....	36
Commercial	37
High BTU	37
Kits.....	37

HOSE ASSEMBLIES & ACCESSORIES

Type I - Brass	26-28
Type I - Steel	28
Type II - Steel	29
Type III - Steel	29
Delivery Hoses	30
SS Flex Connectors.....	30
Hose Supports and Retractors	31
Hose Swivels.....	31

HOSE END COUPLINGS & VALVES	31-32
--	--------------

INTERNAL VALVES

Threaded	12
Flanged.....	13
Repair Kits	13
Accessories	14
Cables, Latches & Releases	14
Air Actuators	14

LIQUID LEVEL VENTS	18
---------------------------------	-----------

PIGTAILS & HOGTAILS	11
--------------------------------------	-----------

PRESSURE GAUGES	40
------------------------------	-----------

QUICK DISCONNECTS	39
--------------------------------	-----------

REGULATORS

First Stage	4
Second Stage	4
2 PSI.....	5
Integral Two Stage.....	5-6
Portable Appliance.....	6
High Pressure	7
Commercial / Industrial.....	8
RV & Camping.....	80

REGULATOR ACCESSORIES

Vent Assemblies	9
Mounting Brackets.....	9
Plug	9
Swivel POL Adaptor.....	9

Pressure Gauge Adaptors, Blocks & Checks	10
--	----

RV & CAMPING EQUIPMENT

Regulators	79
Propane Connectors.....	81-82
Hose Assemblies and Camp-Appliance Hook-Ups.	82

SEALANTS, LEAK DETECTOR, TEFLON TAPE	84
---	-----------

TANK & CYLINDER EQUIPMENT

Multi-Service Valves	68
Filler Valves	68
Internal Relief Valves - ASME & DOT.....	69
Service Valves - Fork Lift and ASME	70
Fixed Liquid Level Gauges.....	70
Internal Relief Valves - Fork Lift.....	70
Fork Lift Acme Connectors	71
Liquid Withdrawal Valves.....	71
Service Valves - ASME & DOT.....	71-72
Type I Cylinder Valves	72
Float Gauges.....	73
Cylinder Filling Valve	73

TOOLS	25
--------------------	-----------

TORCHES & HEATERS

Torch Kits.....	74
Super Ego.....	75
Portable Heaters - Mr Heater / Heat-Star.....	76
Torches and Liquid Burners - Flagro	77-78
Construction Heaters - Flagro	78-79

TUBE STRAPS & CLAMPS	85
---------------------------------------	-----------

TUBING

Copper.....	23
Coated Copper	23
Sleeved Coated Copper	23
Gas (Type G).....	23
Aluminum.....	23
Vinyl / PVC	24

VALVES

Excess Flow	14
Relief	15
Hydrostatic.....	16
External Relief	16
Back Check	16-17
Globe & Angle.....	17

Y STRAINERS	18
--------------------------	-----------

FIRST-STAGE REGULATORS


R122H

Part Number	Capacity BTU/HR Propane ⁽¹⁾	Inlet Connection Inches	Outlet Connection Inches	Outlet Adjustment Range Psig (bar)	Outlet Pressure Setting Psig (bar)
R122H-AAJ	1,100,000	1/4" FNPT	1/2" FNPT	Non-Adjustable	10 (0,69)
R622H-BGK	2,000,000	1/2" FNPT		4 - 6 (0,28 - 0,41)	5 (0,34)
R622H-HGK		FPOL			
R622H-JGK	2,250,000		3/4" FNPT		
R622H-BGJ	2,100,000	1/2" FNPT	1/2" FNPT	8 - 12 (0,55 - 0,83)	10 (0,69)
R622H-DGJ	2,400,000	3/4" FNPT	3/4" FNPT		
R622H-HGJ	2,100,000	FPOL	1/2" FNPT		
R622H-JGJ	2,250,000		3/4" FNPT		
1. Based on 30 psig (2,1 bar) inlet pressure and 20% droop.					

SECOND-STAGE REGULATORS


R222

R622

R652

HSRL

Part Number	Capacity BTU/HR Propane ⁽¹⁾	Inlet Connection Inches	Outlet Connection Inches	Outlet Adjustment Range Inches W.C. (mbar)	Outlet Pressure Setting Inches W.C. (mbar)
R222-BAF	650,000	1/2" FNPT	1/2" FNPT	9 1/2 - 13 (24 - 32)	11 (27)
R622-BCF	875,000		3/4" FNPT	9 - 13 (22 - 32)	
R622-CFF	1,400,000				
R622-DFF					
R652-DFF	1,000,000	3/4" FNPT		3/4" FNPT	9 - 13 (22 - 32)
HSRL-BFC	2,300,000	3/4" FNPT			
HSRL-CFC	2,600,000	1" FNPT	1" FNPT		9 - 13 (22-32)
1. Based on 10 psig (0,69 bar) inlet pressure and 20% droop.					

2 PSI SERVICE REGULATORS



R622E

Part Number	Capacity BTU/HR Propane ⁽¹⁾	Connection Inlet x Outlet Inches	Outlet Pressure Range Psig (bar)	Outlet Pressure Setting Psig (bar)
R622E-BCH	1,460,000	1/2" FNPT x 1/2" FNPT	1-2.2 (0,069 - 0,15)	2 (0,14)
R622E-DCH	1,680,000	3/4" FNPT x 3/4" FNPT		

1. Capacity is based on 10 psig (0,69 bar) inlet pressure and 20% droop.

INTEGRAL TWO-STAGE REGULATORS



R632A



R232A

Part Number	Capacity in BTU/HR Propane ⁽¹⁾	Inlet Connection Inches	Outlet Connection Inches	Outlet Adjustment Range Inches W.C. (mbar)	Outlet Pressure Setting Inches W.C. (mbar)
R232A-BBF	550,000	1/4" FNPT	1/2" FNPT	9.5 to 13 (24 to 32)	11 (27)
R232A-BBFKA ⁽³⁾					
R232A-BBFXA ⁽²⁾		FPOL			
R232A-HBF					
R632A-BCF	850,000	1/4" FNPT	1/2" FNPT	9 to 13 (24 to 32)	
R632A-CFF	950,000		3/4" FNPT		
R632A-JFF	850,000	FPOL	3/4" FNPT		

1. Based on 30 PSIG (2.07 BAR) inlet pressure and 2 inches w.c. (5 mbar) droop.
2. First and second-stage spring case vents opposite gauge taps.
3. R232A-BBF with K805 PIGTAIL.

INTEGRAL TWO-STAGE REGULATORS


R632E

R232E

Part Number	Capacity BTU/HR Propane ⁽¹⁾	Inlet Connection Inches	Outlet Connection Inches	Outlet Adjustment Range Psig (bar)	Outlet Pressure Setting Psig (bar)		
R232E-BBH	500,000	1/4" FNPT	1/2" FNPT	1-2.2 (0,069 - 0,15)	2 (0,14)		
R232E-HBH		FPOL					
R632E-BCH	850,000	1/4" FNPT					
R632E-CFH	850,000					3/4" FNPT	

1. Based on 30 psig (2,1 bar) inlet pressure and 2 inches w.c. (5 mbar) droop.

SMALL PORTABLE APPLIANCE REGULATORS


TYPE 912/101

Regulator Type	Capacities in BTU/HR Propane ⁽¹⁾	Connection Sizes Inches	Outlet Pressure Inches WC (mbar)
912/101	110,000	1/4" x 3/8" FNPT	11 (27)

1. Capacities based on 10 psig (0,69 bar) inlet pressure and 2-inches w.c. (5 mbar) droop.

HIGH PRESSURE REGULATORS


64 SERIES

67CW

67CH

67CD

Part Number	Description	Capacity BTU/HR Propane	Outlet Pressure Setting Psig (bar)	Outlet Adjustment Range Psig (bar)	Inlet & Outlet Connections Inches
64/33	Basic Regulator	2,625,000	10 (0,69)	3-15 (0,21 - 1,03)	1/2" FNPT
64/35		3,600,000	20 (1,38)	5-35 (0,35 - 2,41)	
64/36		4,150,000	40 (2,76)	30-60 (2,07 - 4,14)	
64/222		5,250,000	50 (3,45)	35-100 (2,41 - 6,90)	
64SR/23	With Internal Relief Valve	3,600,000	20 (1,38)	5-35 (0,34 - 2,41)	
67CW-683	Basic Regulator (Wrench Adjustment)	675,000	15 (1,03)	3-20 (0,21 - 1,38)	1/4" FNPT
67CW-684		750,000	20 (1,38)	3-35 (0,21 - 2,41)	
67CH-751	Basic Regulator (Handwheel Adjustment)	675,000	15 (1,03)	3-20 (0,21 - 1,38)	
67CH-743		750,000	20 (1,38)	3-35 (0,21 - 2,41)	
67CH-742		1,200,000	40 (2,76)	30-60 (2,1 - 4,14)	
67CH-741		1,000,000	50 (3,45)	50-135 (3,4 - 9,31)	
67CD-101	Dial Cap Adjustment	750,000	20 (1,38)	5-30 (0,34 - 2,1)	
67CD-102		1,200,000	40 (2,76)	20-50 (1,38 - 3,45)	
67CD-103		1,000,000	50 (3,45)	40-100 (2,76 - 6,9)	

1. Based on inlet pressure 20 psig (1,38 bar) greater than outlet with 20% droop; Liquid capacity = 160 GPH.

2. Based on inlet pressure 20 psig (1,38 bar) greater than outlet with 20% droop; Liquid capacity = 3 to 5 GPH (11 to 19 l/hr).

COMMERCIAL/INDUSTRIAL - HIGH PRESSURE REGULATORS

630

627

Part Number	Capacity BTU/HR Propane ⁽¹⁾	Orifice Size, Inches (mm)	Inlet & Outlet Connections Inches	Outlet Pressure Range Psig (bar)	Outlet Pressure Setting Psig (bar)	Maximum Operating Inlet Pressure Psig (bar)
627-5810	6,080,000	7/8"	3/4" FNPT	5-20 (0,34 -1,38)	10 (0,69)	250 (17,2)
627-6210	10,755,000	1/2"				
627-7710	10,773,000					
630-104/78	14,000,000		2" FNPT	8-20 (0,55 - 1,38)		
1. Based on inlet pressure 20 psig (1,38 bar) greater than outlet with 20% droop.						

COMMERCIAL/INDUSTRIAL - LOW PRESSURE REGULATORS

Cs200

Cs400

Part Number	Capacity BTU/HR Propane	Orifice Size, Inches (mm)	Inlet & Outlet Connections Inches	Outlet Pressure Range Psig (bar)	Outlet Pressure Setting Psig (bar)	Maximum Operating Inlet Pressure Psig (bar)
CS200IR-6EC6	3,900,000 ⁽¹⁾	1/2" (12,7mm)	1-1/4" FNPT	10-14 (0,25 - 0,35)	11 (27)	42 (2,8)
CS400IR-8EC6	6,800,000 ⁽¹⁾	3/4" (19,1mm)	1-1/4" FNPT			20 (1,4)
CS400IR-8EC7	7,600,000 ⁽¹⁾		1-1/2" FNPT			

1. Capacities based on inlet pressure of 10 psig (0,69 bar), Internal Registration and 2-inches w.c. (5 mbar) droop.

REGULATOR ACCESSORIES



ANGLE TYPE



P100A



P100C

VENT ASSEMBLIES			
Body Size Inches	Stabilizer	Umbrella Type	Part Number
3/4" FNPT	No	---	Y602-9

MOUNTING BRACKETS		
Regulator Part Number	Triangular Part Number	Bowtie Part Number
R622, R632A, R642, R622H	P100A	P100C
R122H, R222 & R232A		---
912		---



P500

P500 Plug


Keeps dirt and foreign material from entering changeover assemblies. 1/4-inch Inverted Flare.



M322

SWIVEL POL ADAPTORS			
Part Number	POL Connection	Other Connection	Length, Inches (mm)
M322	Straight Male POL	1/4 MNPT	3-1/2" (89mm)

REGULATOR ACCESSORIES



J600



50P-2

PRESSURE GAUGE ADAPTOR & TEST BLOCK

Type J600 test block connects to the container valve to check for leaks in the downstream system.
Male POL x Female POL, test block with 0 – 300 psig gauge.



P400



50-2



50P-5

TEE BLOCKS

Tee Block (Without Check)	Pigtail or Piping Connection	Regulator Connection Inches
P403	Female POL	Female POL
P400		Male POL

TEST GAUGE ASSEMBLIES

Part Number	Inlet Connections Inches	Hose	Plastic	Ranger Inches W.C. (mbar)
50-2	1/4" MNPT	No	No	0 to 35 (0 to 87 mbar)
50P-2	Female Hose	Yes	Yes	
50P-5		Yes	No	

MARSHALL EXCELSIOR PIGTAILS AND HOGTAILS



Part Number	Marshall Part Number	Description
K160	ME1662-20	MPOL x MPOL, 20", 1/4" Tube, 1-1/8" Hex
K162	ME1662-36	MPOL x MPOL, 36", 1/4" Tube, 1-1/8" Hex
K166	ME1662-48	MPOL x MPOL, 48", 1/4" Tube, 7/8" Hex
K200	ME1680L-20	MPOL x MPOL, 20", 3/8" Tube, 1-1/8" Hex
K240	ME1663-20	MPOL x 1/4" I.F., 20", 1/4" Tube, 1-1/8" Hex
K249	ME1663-36	MPOL x 1/4" I.F., 36", 1/4" Tube, 1-1/8" Hex
K280	ME1679-20	MPOL x 1/4" MNPT, 20", 1/4" Tube, 1-1/8" Hex
K460	ME1689-12	MPOL x 1/4" MNPT, 12", 3/8" Tube, 7/8" Hex
K520	ME1648L-12	MPOL x 1/2" MNPT, 12", 3/8" Tube, 7/8" Hex
K805	ME1669-20	MPOL x 1/4" MNPT, 20", 1/4" Tube, 7/8" Hex
K807	ME1669-06	MPOL x 1/4" MNPT, 6", 1/4" Tube, 7/8" Hex
K810	ME1669-12	MPOL x 1/4" MNPT, 12", 1/4" Tube, 7/8" Hex
K832	ME1684-12	MPOL x 1/2" MNPT, 12", 3/8" Tube, 7/8" Hex
K840	ME1664-20	MPOL x MPOL, 20", 1/4" Tube, 7/8" Hex
K845	ME1664-12	MPOL x MPOL, 12", 1/4" Tube, 7/8" Hex
K846	ME1664-36	MPOL x MPOL, 36", 1/4" Tube, 7/8" Hex
K860	ME1680-20	MPOL x MPOL, 20", 3/8" Tube, 7/8" Hex
K862	ME1680-12	MPOL x MPOL, 12", 3/8" Tube, 7/8" Hex
ME1680-48	ME1680-48	MPOL x MPOL, 48", 3/8" Tube, 7/8" Hex
K880	ME1665-20	MPOL x 1/4" I.F., 20", 1/4" Tube, 7/8" Hex
K885	ME1665-36	MPOL x 1/4" I.F., 36", 1/4" Tube, 7/8" Hex

FISHER THREADED INTERNAL VALVES



THREADED INTERNAL VALVES						
Connections Inlet x Outlet Inches	Part Number		Closing Flow GPM Propane		Vapor Capacity SCFH Propane	
	Straight Body	Tee Body	Half Coupling	Full Coupling	25 Psig (1,72 bar) Inlet	100 Psig (6,90 bar) Inlet
1-1/4" MNPT x 1-1/4" FNPT	C407-10-05	---	50	35	7,800	13,200
	C407-10-08		80	65	11,200	19,200
2" MNPT x 2" FNPT	C477-16-10	C471-16-10	100	60	26,000	45,000
	C477-16-25	---	250	130	---	---
3" MNPT x 3" FNPT	C477-24-46	C471-24-46	460	380	---	---
1. Includes a factory installed P340 / P341 latch.						

FISHER FLANGED INTERNAL VALVES

C404-32

4-INCH FLANGED INTERNAL VALVES					
Cable Part Number ⁽¹⁾	Inlet	Outlet	Closing Flow GPM Propane ⁽²⁾	Vapor Capacity SCFH Propane	
				25 Psig Inlet (1,72 bar)	100 Psig Inlet (6,90 bar)
C404-32-60	4/100 CL300 ASME RF Modified 5-7/8 dia. Bore	4/100 CL300 ASME RF	600	83,200	141,500
1. 4-inch size available in single flange only. 2. Closing flow vertical down.					

REPAIR KITS	
Part Number	Internal Valve Series
RC400-16T012	2" C402, C421, C427
RC403-24T012	C403-24
RC404-24T012	C404-24
RC407-10T012	C407-10

FISHER INTERNAL VALVE ACCESSORIES


P650

P341

Internal Valve Size Inches	Primary Cable Control	Cable Assembly	Latch/Release Mechanism	Fusible Link
1-1/4" , 2" & 3" (Threaded or Flanged)	P650	Included with P650	P341	P134
4" Flanged	Use Allegheny or Wheaton Control	-	-	

FISHER AIR ACTUATORS


P389

P639A

P614

Internal Valve Part Number	Air Cylinder Part Number	Maximum Inlet Pressure to Cylinder, PSIG (bar)	Minimum Operating Pressure to Activate Internal Valve, PSIG (bar)
C471/C477	P639A	125 (8,6)	20 (1,4)
C404-32	P614	125 (8,6)	20 (1,4)
C407-10	P389	250 (17,2)	60 (4,1)

EXCESS FLOW VALVES


F101

F131

F133

F138

Part Number	Material	Application	Inlet Connection Inches	Outlet Connection Inches	UL Rated Closing Flow, Propane (Horizontal Position)			PSID
					Liquid GMP	Vapor SCFH		
						25 Psig (1,72 bar) Inlet	100 Psig (6,90 bar) Inlet	
F138	Brass	In-Line	1/4" MNPT	1/4" FNPT	1.8	377	641	1.4
F101	Brass	Tanks (Full or Half Coupling)	3/4" MNPT	3/4" FNPT	20	3,459	5,880	8.5
F131	Brass	In-Line	1-1/2" FNPT	1-1/2" FNPT	60	11,694	19,877	4.7
F133	Brass	In-Line	2" FNPT	2" FNPT	155	29,202	49,718	4.2

FISHER RELIEF VALVES

Type 1805 – relief valve is designed for installation between the First and Second-Stage regulators or in the downstream line from a high pressure regulator used for a Final-Stage service. Available in 1 or 2-inch valve bodies.



TYPE 1805

DIAPHRAGM RELIEF VALVES					
Part Number	Body Size, Inches	RELIEF PRESSURE SETTING, Psig (bar)	RELIEF ADJUSTMENT RANGE, Psig (bar)	PROPANE RELIEF CAPACITY AT FOLLOWING PRESSURE BUILD-UP OVER RELIEF SETTING	
				Build-up over set pressure, Psig / bar	Capacity, SCFH/SCMH
1805-19P	1" FNPT	30 / 2,1	10 to 60 / 0,69 to 4,1	15 / 1,0	2,840 / 80,4
1805-52P	2" FNPT		10 to 50 / 0,69 to 3/4		12,000 / 340

SQUIBB TAYLOR HYDROSTATIC RELIEF VALVE

Part Number	Description
A1327	Hydrostatic Relief Valve 1/4" MNPT, 350 PSI, Stainless Steel




A1327

FISHER™

FISHER EXTERNAL RELIEF VALVES



P206



H185

Part Number	Container Type	Start-To-Discharge Setting Psig / bar	Container Connection, Inches	Flow Capacity, SCFM AIR	Accessory Part Numbers	
				UL	Pipeaway Adaptor	Protective Cap
H110-250	ASME	250 (17,24)	1/4" MNPT	310	---	P206
H185-250			3/4" MNPT	2,223	---	---
H110-312		312 (21,51)	1/4" MNPT	390	---	P206
H173	DOT & Hydrostatic Relief	375 (25,86)	3/4" MNPT	903 ¹	(1/2 FNPT)	
H123			1/4" MNPT	---	---	

1. DOT cylinder water capacity 500 lbs., approved by Bureau of Explosive and CGA

FISHER™

FISHER BACK-CHECK VALVES



G100



G200

Seat Construction	Container or Inlet Connection Inches	Outlet Connection Inches	Propane Flow Capacity at 10 Psig (0,69 bar) Differential	Part Number			
				Brass	Steel	Ductile Iron	
						No Flow Indicator	Flow Indicator
Metal-to-Metal	3/4" MNPT	3/4" FNPT	21 GPM	G100	---	---	---
Soft Seat	2" FNPT	2" FNPT	200 GPM	---	---	G200-16	---

MARSHALL HIGH FLOW BACK CHECK VALVE



ME870-6

Part Number	Description	Material	Propane Flow 10 PSIG Differential Pressure
ME870-6	3/4" FNPT x 3/4" MNPT Back Pressure Check Valve with Removable Soft Seat	Brass	24

FISHER

GLOBE & ANGLE VALVES



N310



N410



N450

Service	Inlet & Outlet Connections Inches	Part Number			
		Globe		Angle	
		Fisher	Marshall Excelsior	Fisher	Marshall Excelsior
LP-Gas & NH	3/4" FNPT	---	ME825-6	N401-06	ME815-6
	1" FNPT	---	ME825-8	N401-08	ME815-8
	1-1/4" FNPT	---	---	N410-10	---
	2" FNPT	N310-16	ME825-16	---	ME815-16

Economy Version

LP-Gas	3/4" FNPT	---	---	N450-06	---
--------	-----------	-----	-----	---------	-----

MARSHALL LIQUID LEVEL VENT VALVE

Type J415 with steel construction for use on either LP-Gas or NH service. Installed on large bulk storage tanks at the 3 maximum filling level. Standard valve comes with a 3/4 inch MNPT container connection and two 1/4 inch FNPT side outlets.



J415

MARSHALL Y STRAINERS



Ductile iron
FNPT connections: 1/4" to 1-1/2"

SCREWED END Y STRAINERS	
Part Number	Size
DYS-12	3/4" connections, with reducing bushing
DYS-20	1-1/4" connections, with reducing bushing
DYS-24	1-1/2" connections, with reducing bushing

MARSHALL ACME COUPLINGS & ADAPTORS

FEMALE ACME FILLER COUPLINGS

Female Acme Inches	Other Connection Inches	Length Inches (mm)		Part Number	
				Brass	Steel
1-1/4"	3/8" MNPT	3" (76mm)	1	M100	
1-1/4"	1/2" MNPT	2-1/2" (64mm)	1		
1-3/4"	1/2" MNPT	3" (76mm)	1	M110	
1-3/4"	3/4" MNPT	3" (76mm)	1	M111	M631-6
1-3/4"	3/4" MNPT	6-1/8" (156mm)	2		
1-3/4"	1" MNPT	3" (76mm)	1		M631-8
1-3/4"	1" MNPT	7" (178mm)	2		M635-8
2-1/4"	1-1/4" MNPT	3-1/4" (83mm)	3	M120 ¹	M121
3-1/4"	1-1/4" MNPT	1-1/2" (38mm)	4	M442	
3-1/4"	2" MNPT	3-3/4" (95mm)	3	M130 ¹	M133
4-1/4"	3" MNPT	4-1/2" (114mm)	3		

1. Steel Nipple

FEMALE ACME VAPOUR RETURN COUPLINGS

Female Acme	Male NPT Inches	Length Inches (mm)		Part Number	
				Brass	Steel
1-1/4"	3/8"	2-1/2" (64mm)	5		
1-1/4"	1/2"	2-1/2" (64mm)	5	M141	
1-3/4"	3/4"	3-3/8" (86mm)	5		
1-3/4"	1"	3-1/4" (83mm)	5		
2-1/4"	1-1/4"	3-3/8" (86mm)	6	M160	

MALE ACME X FEMALE NPT ADAPTORS

Male Acme Inches	Female NPT Inches		Part Number		Washer Drawing No.
			Brass	Steel	
1-1/4"	3/8"	8	M498-6/3		1E8122-03022
1-1/4"	1/2"	8			1E8122-03022
1-1/4"	3/4"	7	M193		1E8122-03022
1-5/16"	1/4"	10	ME393-1		1E8122-03022
1-3/4"	1/4"	7	M210		1E8124-03022
1-3/4"	3/8"	7			1E8124-03022
1-3/4"	1/2"	7			1E8124-03022
1-3/4"	3/4"	7		M526-6	1E8124-03022
1-3/4"	1"	7	M214	M526-8	1E8124-03022
2-1/4"	1"	8			1E8126-03022
2-1/4"	1-1/4"	8	M502-16/10	M522-16/10	1E8126-03022
2-1/4"	1-1/2"	8			1E8126-03022
3-1/4"	1-1/4"	7			1E8128-03022
3-1/4"	2"	7	M252	M528-16	1E8128-03022
3-1/4"	3"	7			1E8128-03022



1



2



3



4



5



6



7



8



9



10

MALE ACME ADAPTORS

Male Acme Inches		Part Number		Washer Drawing No.
		Brass	Steel	
1-1/4 x 1-1/4	9			1E8122-03022
1-3/4 x 1-3/4	9	M273	M536-14	1E8124-03022
2-1/4 x 2-1/4	9	ME275		1E8126-03022
3-1/4 x 3-1/4	9	ME277	M536-26	1E8128-03022

COUPLINGS & ACME ADAPTORS



M233

MALE ACME X MALE NPT ADAPTORS				
Male Acme Inches	Male NPT Inches	Part Number		Washer Drawing No.
		Brass	Steel	
1-1/4"	1/2"	---	---	1E8122-03022
	1"	---	---	
1-3/4"	3/4"	---	---	1E8124-03022
	1"	---	M521-8	
	1-1/4"	---	---	
2-1/4"	1-1/4"	M233	---	1E8128-03022
3-1/4"	2"	M503-16	M263	1E8128-03022
	3"	---	---	

Maximum allowable Working Pressure 400 Psig (27,58 bar)



M306

ADAPTOR ASSEMBLIES	
Part Number	Description
M306	F. CGA 555 Inlet x 1/4" MNPT Outlet Adaptor Assy
M308	F. CGA 555 Inlet x F. POL



ME399

CONVERSION ADAPTOR	
Part Number	Description
ME399	1-5/16" M. Acme x F. POL x 1/4" MNPT Adaptor with Quick Closing Shutoff Poppet



M455

LIQUID WITHDRAWAL ADAPTOR	
Part Number	Description
M455	3/4" Male NGT Inlet x 3/4" MNPT Outlet

FILLER VALVE ADAPTOR	
 M450A M450A allows Methanol to be added through conventional designed double back check filler valves with a 1-3/4-inch male ACME filler connection and 3/4-inch FNPT outlet.	



M357

SINGLE PIECE POL ADAPTORS		
Part Number	POL Connection	Other Connection Inches
Brass	Male POL	1/2" FNPT
M357		



M390



ME516



ME790

FILLER COUPLINGS	
Part No.	Description
M390	Soft Nose Male POL x 1/4" MNPT - Brass - Nipple -6" O.A.L.
M390S	Soft Nose Male POL x 1/4" MNPT - Stainless Steel - Nipple - 6" O.A.L.
ME516	1-5/16" Female Acme x 1/4" MNPT - 6" O.A.L.
ME790	1-1/4" Female Acme x 1/4" MNPT



M112

HOSE END ADAPTOR	
Part Number	Description
M112	1-3/4" F.ACME x 1" MPT Filler Coupling, Brass



ME572

FILL ADAPTORS	
Part Number	Description
ME572	1-3/4" F. Acme x 1-3/4" M. Acme Filler Body Swivel
ME574	1-3/4" F. Acme x 1-3/4" M. Acme Filler Body Swivel with Vent Valve



M178

PLUGS	
Dust Seal	Size Inches
M178 plastic	1-1/4" M. Acme
M179 plastic	1-3/4" M. Acme
M180 ¹ plastic	2-1/4" M. Acme
M181 plastic	3-1/4" M. Acme

¹Available with Chain

MARSHALL ACME ADAPTOR ACCESSORIES



M612



ME614



M108 OR M109



M219

ADAPTOR CAPS			
Part Number		Female Acme Inches	Male Acme Inches
Brass	Steel		
M611		2-1/4"	1-3/4"
M612	M622	3-1/4"	1-3/4"
M613	M623	4-1/4"	3-1/4"
ME614	- - -	3-1/4"	2-1/4"



M431



ME441F-1

FEMALE ACME CAPS			
Size F. Acme Inches	Part Number		
	Plastic ⁽¹⁾	Brass	Steel
1-1/4"	M108		
1-3/4"	M109		M219 ²
2-1/4"		M431	
3-1/4"	M181	M441	M443
4-1/4"			

1. For LP-Gas Only.
2. Add - 1 suffix for ring & chain.

FEMALE ACME CAPS PLUG WITH KNOB & CHAIN	
Part Number	Description
ME431F-1	2-1/4" Female Acme Cap, Brass
ME441F-1	3-1/4" Female Acme Cap, Brass
ME441FS-1	3-1/4" Female Acme Cap, Steel



P147/P148



P167



P120B

SPANNER WRENCH		
Part Number	Overall Length Inches (mm)	Construction Material
P120B	18" (457mm)	Aluminum

RING & CHAIN ASSEMBLIES			
Part Number	For Cap or Dust Seal Size Inches	Type Number	
		Cap	Dust Seal
P147	1-1/4" Acme	M108	M178
P147 ⁽¹⁾	1-3/4" Acme	M109 or M219	
P148 ⁽¹⁾	1-3/4" Acme	M109	M179
P148	2-1/4" Acme		M180
P167	2-1/4" Acme	M431	
P167	3-1/3" Acme	M441 or M443	
P167	4-1/4" Acme		

1. P147 fits 3/4 inches pipe size.
2. P148 fits 1-1/4 inch pipe size.

SERVICEMAN'S REPLACEMENT KIT

Part Number	Description		
MEW1	Complete Serviceman's Seal Kit and Carrying Case Includes:		
	Part No.*	Qty	Description
	1E8124-03022	10	1-3/4" Acme Flat Gaskets
	1E8122-03022	10	1-1/4" Acme Flat Gaskets
	RI14101014	9	1-1/4" Acme Forklift Flat Gaskets
	1E8126-03022	10	2-1/4" Acme Flat Gaskets
	1E8128-03022	10	3-1/4" Acme Flat Gaskets
	RI140007	12	Male Forklift Connector O-rings
	D110	12	POL O-rings

* Not available separately



MEW1

QUICK ACTING TOGGLE VALVES



ME792C



ME796

ME791C

Part Number	Description			
	Inlet	Outlet	Locking Handle	Bleed Valve
ME791C	1/2" FNPT	1/4" FNPT	No	No
ME791D	1/2" FNPT	1/2" FNPT	No	No
ME792C	1/2" FNPT	1/4" FNPT	Yes	No
ME792D	1/2" FNPT	1/2" FNPT	Yes	No
ME796	QCC Quick Fill Coupling 1-5/16" Acme x 1/4 MNPT			

HOSE COUPLINGS, CLAMP STYLE

Part Number	Coupling Style	Size Inches	Hose I.D. Inches	Approx. Hose I.D. Inches
M3162-16	Clamp Type, Standard Outlet	1" MNPT	1"	1-1/2"
M3162-20		1-1/4" MNPT	1-1/4"	2"



M3162
(Standard Outlet)

METAL TUBING

COPPER TUBING



GENERAL PURPOSE SOFT ANNEALED SEAMLESS BRIGHT FINISH ALSO AVAILABLE IN 50' AND 100' LENGTHS				
Part Number	Wall Thickness Inches	Size		Working Pressure P.S.I
		O.D.	Coil	
DCT-2X25	.030"	1/8	25'	2400
DCT-3X25	.030"	3/16	25'	1600
DCT-4X25	.030"	1/4	25'	1200
DCT-5X25	.032"	5/16	25'	1020
DCT-6X25	.032"	3/8	25'	850
DCT-8X25	.032"	1/2	25'	640
DCT-10X25	.035"	5/8	25'	560
DCT-12X25	.035"	3/4	25'	470

ALUMINUM TUBING ALLOY 3003-0, ASTM B-483				
Part Number	Wall Thickness Inches	Size		Working Pressure P.S.I
		O.D.	Coil	
DALT-3X50	.028"	3/16	50'	1000
DALT-4X50	.032"	1/4	50'	800
DALT-5X50	.035"	5/16	50'	750
DALT-6X50	.035"	3/8	50'	620



TYPE K ASTM B-88					
Part Number	Nominal Size	Wall Thickness Inches	Size		Working Pressure P.S.I
			O.D.	Coil	
DCT-6-049	1/4	.035"	3/8	100'	900
DCT-8-049	3/8	.049"	1/2	100'	990
DCT-10-049	1/2	.049"	5/8	100'	780
DCT-12-049	5/8	.049"	3/4	100'	640

POLYETHYLENE COATED SOFT COPPER TUBING, TYPE L-G/GAS ASTM B-88/B-837				
Part Number	Nominal Size	Wall Thickness Inches	Size	
			O.D.	Coil
DCCT-4X100	1/4	.030"	3/8	100'
DCCT-4X250				250'
DCCT-6X100	3/8	.035"	1/2	100'
DCCT-6X250				250'
DCCT-8X100	1/2	.040"	5/8	100'
DCCT-8X250				250'
DCCT-10X100	5/8	.042"	3/4	100'
DCCT-12X100	3/4	.045"	7/8	100'

Also available in orange for fuel-oil applications and blue for potable water.

TYPE G / GAS ASTM B-837				
Part Number	Nominal Size	Wall Thickness Inches	Size	
			O.D.	Coil
DGCT-6X50 DGCT-6X100	1/4	.030"	3/8	50' 100'
DGCT-8X50 DGCT-8X100	3/8	.035"	1/2	50' 100'
DGCT-10x50	1/2	.045"	5/8	50'

OUTER SLEEVED GAS TUBE POLYETHYLENE COATED SOFT COPPER TUBING, TYPE L-G/GAS ASTM B-88/B-837				
Part Number	Nominal Size	Wall Thickness Inches	Size	
			O.D.	Coil
DCCTP-4X100	1/4	.030"	3/8	100'
DCCTP-6X100	3/8	.035"	1/2	100'
DCCTP-8X100	1/2	.040"	5/8	100'

VINYL/PVC TUBING

CLEAR VINYL TUBING FDA APPROVED - 100' ROLLS

Manufactured with materials compounded from ingredients approved by F.D.A. Tolerances are held very close. Electrically non-conductive and self extinguishing. Lightweight and excellent flexibility.



Temperature Range - 20°F to +150°F
100 Ft. coils unless otherwise specified

Part No.	Size	x Max. W.P. at 70° F
DJFT-42	1/8" I.D.	65 psi
DJFT-53	3/16" I.D.	55 psi
DJFT-64	1/4" I.D.	55 psi
DJFT-75	7/16" I.D.	50 psi
DJFT-86	3/8" I.D.	45 psi
DJFT-106	3/8" I.D.	55 psi
DJFT-108	1/2" I.D.	30 psi
DJFT-128	1/2" I.D.	45 psi
DJFT-1410	5/8" I.D.	40 psi
DJFT-1612	3/4" I.D.	35 psi
DJFT-2016	1" I.D.	25 psi

* At 70°F

CLEAR BRAIDED PVC HOSE FDA APPROVED - 100' ROLLS

Is a clear, high pressure hose, excellent for use with Air, Water, Oil, Chemicals, Acids, Alkalis etc. Made with a High Tensile Synthetic Fibre which offers ruggedness, flexibility and light weight. FDA approved.



Temperature Range - 5°F to +150°F
100 Ft. coils unless otherwise specified

Part No.	Size	x Max. W.P. at 70° F
DPVC-84	1/4" I.D.	250 psi
DPVC-106	3/8" I.D.	225 psi
DPVC-128	1/2" I.D.	200 psi
DPVC-1410	5/8" I.D.	200 psi
DPVC-1712	3/4" I.D.	150 psi
DPVC-2116	1" I.D.	125 psi
DPVC-2820	1-1/4" I.D.	100 psi

* At 70°F

TOOLS

TUBING CUTTERS



Model Number	Capacity
DTC-15	1/4" through 2-5/8"

QUICK ACTION TUBING CUTTER

- Spring loaded cutter wheel feeding system allows slide action adjustment and quick release.
- Reinforced monoblock aluminum body and slide bar with stop to protect cutting wheels.
- Extra long grooved rollers for close-to-flare cuts and knob of ergonomic design.
- Detachable reamer supplied with the cutter and located inside the frame.

MULTI-PURPOSE CUTTER

Ideal for synthetic and rubber hose - plastic tubing - PVC pipe - copper wire. 12 volt battery cable handles are insulated with plastic covering and may be locked when not in use. Maximum capacity 1-1/8" O.D. Replacement blade supplied with each cutter ordered.



Part Number	Description
DMPC-1	Tool
DMPC-Blade	Blade Only

TUBE CUTTER

For Non-Metallic Tubing



Part Number	Capacity
DPTC-3	1/8" O.D. to 1/2" O.D.

SPRING-TYPE TUBE BENDER



Model Number	Tube O.D.
DTB-4	1/4"

Used for free form bending of soft copper and aluminum tube. Spring wire is proportioned to tube size to allow shorter radius bends on small tube.

(TYPE I) APPROVED HOSE ASSEMBLIES - BRASS ENDS

All Dominion Fittings Hose Assemblies are C.S.A. approved. Used throughout the propane industry on recreational vehicles, camping equipment, torches, construction heaters, tank manifolds, etc.

Working Pressure: up to 350 P.S.I.

Can be used for natural gas with application specific criteria (Max 50 P.S.I., outside use only, not for use with Compressed Natural Gas (CNG))

ORDERING INFORMATION

- A) Substitute length in inches where 00's appear in Series Number
B) Specify Overall Length if "Tip to Tip" measurements are critical.



MALE PIPE BOTH ENDS			
Series	I.D.	1	2
D2600-4	1/4"	1/4"	1/4"
D2600-6	3/8"	1/4"	1/4"
D3500-4	1/4"	3/8"	3/8"
D3500-6	3/8"	3/8"	3/8"
D5100-8	1/2"	1/2"	1/2"



MALE PIPE X FEMALE 45° SAE			
Series	I.D.	1	2
D2700-4	1/4"	1/4"	3/8"
D2700-6	3/8"	1/4"	3/8"
D2800-4	1/4"	3/8"	3/8"
D2800-6	3/8"	3/8"	3/8"
D2900-6	3/8"	3/8"	1/2"
D6400-8	1/2"	1/2"	1/2"
D6600-4	1/4"	1/8"	3/8"
D8100-6	3/8"	1/2"	3/8"



FEMALE 45° SAE SWIVEL BOTH ENDS			
Series	I.D.	1	2
D4700-4	1/4"	1/4"	1/4"
D4800-4	1/4"	3/8"	3/8"
D4800-6	3/8"	3/8"	3/8"
D6700-6	3/8"	1/2"	1/2"
D6700-8	1/2"	1/2"	1/2"



FEMALE SAE X LEFT HAND SWIVEL			
Series	I.D.	1	2
D4400-4	1/4"	3/8"	9/16"-18LH
D4400-6	3/8"	3/8"	9/16"-18LH



MALE PIPE X LEFT HAND SWIVEL			
Series	I.D.	1	2
D4100-4	1/4"	1/4"	9/16"-18LH
D4100-6	3/8"	1/4"	9/16"-18LH
D4200-4	1/4"	3/8"	9/16"-18LH
D4200-6	3/8"	3/8"	9/16"-18LH



LEFT HAND SWIVEL BOTH ENDS			
Series	I.D.	1	2
D3400-4	1/4"	9/16"-18LH	9/16"-18LH
D3400-6	3/8"	9/16"-18LH	9/16"-18LH
D34120-4	1/4"	9/16"-18LH	9/16"-18LH
D34180-4	1/4"	9/16"-18LH	9/16"-18LH
D34240-4	1/4"	9/16"-18LH	9/16"-18LH
D34300-4	1/4"	9/16"-18LH	9/16"-18LH
D34360-4	1/4"	9/16"-18LH	9/16"-18LH



MALE PIPE X FEMALE PIPE			
Series	I.D.	1	2
D2400-4	1/4"	1/4"	1/4"
D2400-6	3/8"	1/4"	1/4"
D2500-4	1/4"	3/8"	3/8"
D2500-6	3/8"	3/8"	3/8"



MALE PIPE X MALE 45° SAE			
Series	I.D.	1	2
D3000-4	1/4"	3/8"	3/8"
D3000-6	3/8"	3/8"	3/8"

(TYPE I) APPROVED HOSE ASSEMBLIES - BRASS ENDS



RIGHT HAND SWIVEL BOTH ENDS			
Series	I.D.	1	2
D2300-4	1/4"	9/16"-18RH	9/16"-18RH
D2300-6	3/8"	9/16"-18RH	9/16"-18RH



MALE POL X MALE PIPE			
Series	I.D.	1	2
D3600-4	1/4"	SNMPOLXF	1/4"
D3600-6	3/8"	SNMPOLXF	1/4"
D3700-4	1/4"	SNMPOLXF	3/8"
D3700-6	3/8"	SNMPOLXF	3/8"



MALE POL X FEMALE 45° SAE			
Series	I.D.	1	2
D5000-4	1/4"	1/8"	3/8"
D5000-6	3/8"	1/8"	3/8"



MALE 45° SAE BOTH ENDS			
Series	I.D.	1	2
D3800-4	1/4"	3/8"	3/8"




MALE POL X LEFT HAND			
Series	I.D.	1	2
D3300-4	1/4"	SNMPOLXF	9/16"-18LH
D3300-6	3/8"	SNMPOLXF	9/16"-18LH



INV. FLARE X FEMALE PIPE			
Series	I.D.	1	2
D2100-4	1/4"	1/4"	1/4"



MALE POL X MALE PRIMUS			
Series	I.D.	1	2
D3900-4	1/4"	SNMPOLXF	1" - 20M
D3900-4HWS	1/4"	SNPLOXF HANDWHEEL	1"-20M



MALE PRIMUS X FEMALE PRIMUS			
Series	I.D.	1	2
D4000-4	1/4"	1"-20M	1"-20F




MALE POL X FEMALE PRIMUS			
Series	I.D.	1	2
D4500-4	1/4"	SNMPOXF	1" - 20F
D4500-4HWS	1/4"	SNMPOXF HANDWHEEL	1"-20F



MALE POL BOTH ENDS			
Series	I.D.	1	2
D3100-4	1/4"	SNMPOLXF	SNMPOL
D3100-6	3/8"	SNMPOLXF	SNMPOL
D4900-4	1/4"	SNMPOL	SNMPOL
D4900-6	3/8"	SNMPOL	SNMPOL



MALE POL X FEMALE 45° SAE			
Series	I.D.	1	2
D4300-4	1/4"	SNMPOLXF	3/8"
D4300-6	3/8"	SNMPOLXF	3/8"



BLACK FQCC X INV. FL.			
Series	I.D.	1	2
D8400-4	1/4"	BFQCC	1/4"



MALE POL X MALE INV. FL.			
Series	I.D.	1	2
D3200-4	1/4"	SNMPOLXF	1/4"



MALE PIPE X POL HARDNOSE			
Series	I.D.	1	2
D8200-4	1/4"	1/4"	POLH
D8300-4	1/4"	1/2"	POLH



BLACK FQCC X MALE PIPE			
Series	I.D.	1	2
D8500-4	1/4"	BFQCC	1/4"

(TYPE I) APPROVED HOSE ASSEMBLIES - BRASS ENDS



GREEN FQCC X INV. FL.			
Series	I.D.	1	2
D8600-4	1/4"	GFQCC	1/4"



BLACK FQCC X MALE PRIMUS			
Series	I.D.	1	2
D8800-4	1/4"	BFQCC	1"-20M



GREEN FQCC X MALE PRIMUS			
Series	I.D.	1	2
D9000-4	1/4"	GFQCC	1"-20M



GREEN FQCC X MALE PIPE			
Series	I.D.	1	2
D8700-4	1/4"	GFQCC	1/4"



MALE PIPE X MALE PRIMUS			
Series	I.D.	1	2
D8900-4	1/4"	1/4" MNPT	1"-20M



FEMALE PIPE X MALE PRIMUS			
Series	I.D.	1	2
D9100-4	1/4"	1/4" FNPT	1"-20M

(TYPE I) APPROVED HOSE ASSEMBLIES - STEEL ENDS



MALE PIPE X MALE PIPE			
Series	I.D.	1	2
DS2600-4	1/4"	1/4"	1/4"
DS3500-6	3/8"	3/8"	3/8"
DS5100-8	1/2"	1/2"	1/2"
DS5200-12	3/4"	3/4"	3/4"
DS5300-16	1"	1"	1"
DS5400-20	1-1/4"	1-1/4"	1-1/4"
DS5500-24	1-1/2"	1-1/2"	1-1/2"
DS5600-32	2"	2"	2"



MALE PIPE X FEMALE JIC			
Series	I.D.	1	2
DS5700-4	1/4"	1/4"	1/4"
DS5800-6	3/8"	3/8"	3/8"
DS5900-8	1/2"	1/2"	1/2"
DS6000-12	3/4"	3/4"	3/4"
DS6100-16	1"	1"	1"
DS6200-20	1-1/4"	1-1/4"	1-1/4"
DS7000-32	2"	2"	2"



FEMALE JIC X FEMALE JIC			
Series	I.D.	1	2
DS7100-4	1/4"	1/4"	1/4"
DS7200-6	3/8"	3/8"	3/8"
DS7300-8	1/2"	1/2"	1/2"
DS7400-12	3/4"	3/4"	3/4"
DS7500-16	1"	1"	1"
DS7600-20	1-1/4"	1-1/4"	1-1/4"
DS7800-32	2"	2"	2"



MALE PIPE X FEMALE SAE			
Series	I.D.	1	2
DS2700-4	1/4"	1/4"	1/4"
DS2800-6	3/8"	3/8"	3/8"
DS6400-8	1/2"	1/2"	1/2"
DS6500-12	3/4"	3/4"	3/4"



FEMALE SAE BOTH ENDS			
Series	I.D.	1	2
DS4800-4	1/4"	1/4"	1/4"
DS4800-6	3/8"	3/8"	3/8"
DS6700-8	1/2"	1/2"	1/2"
DS6800-12	3/4"	3/4"	3/4"



MALE PIPE X FEMALE PIPE			
Series	I.D.	1	2
DS7900-12	3/4"	3/4"	3/4"

(TYPE II) APPROVED HOSE ASSEMBLIES - STEEL ENDS

All Dominion Fittings Hose Assemblies are C.S.A. approved. Used throughout the propane industry - on bulk delivery trucks, pumping systems, metering systems, bulk plants, loading arms, etc.

Working Pressure: up to 350 P.S.I.

ORDERING INFORMATION

- A) Substitute length in inches where 00's appear in Series Number
B) Specify Overall Length if "Tip to Tip" measurements are critical.



MALE PIPE X MALE PIPE			
Series	I.D.	1	2
DSTR5100-8	1/2"	1/2"	1/2"
DSTR5200-12	3/4"	3/4"	3/4"
DSTR5300-16	1"	1"	1"
DSTR5400-20	1-1/4"	1-1/4"	1-1/4"
DSTR5600-32	2"	2"	2"



FEMALE JIC X FEMALE JIC			
Series	I.D.	1	2
DSTR7300-8	1/2"	1/2"	1/2"
DSTR7400-12	3/4"	3/4"	3/4"
DSTR7500-16	1"	1"	1"
DSTR7600-20	1-1/4"	1-1/4"	1-1/4"
DSTR7800-32	2"	2"	2"



FEMALE SAE X FEMALE SAE			
Series	I.D.	1	2
DSTR6700-8	1/2"	1/2"	1/2"
DSTR6800-12	3/4"	3/4"	3/4"
DSTR6900-16	1"	1"	1"



MALE PIPE X FEMALE JIC SWIVEL			
Series	I.D.	1	2
DSTR5900-8	1/2"	1/2"	1/2"
DSTR6000-12	3/4"	3/4"	3/4"
DSTR6100-16	1"	1"	1"
DSTR6200-20	1-1/4"	1-1/4"	1-1/4"
DSTR7000-32	2"	2"	2"

(TYPE III) APPROVED HOSE ASSEMBLIES - STEEL ENDS

All Dominion Fittings Hose Assemblies are C.S.A. approved. Used throughout the propane industry for use with Liquefied Petroleum Gas (LPG) and Compressed Natural Gas (CNG)

Working Pressure: up to 350 P.S.I.
Temperature range -40° C to +60° C (-40° F to +140° F)

ORDERING INFORMATION

- A) Substitute length in inches where 00's appear in Series Number
B) Specify overall length if "Tip to Tip" measurements are critical.



MALE PIPE X FEMALE SAE			
Series	I.D.	1	2
DCAR2700-6	3/8"	1/4"	3/8"



FEMALE SAE X FEMALE SAE			
Series	I.D.	1	2
DCAR4800-6	3/8"	3/8"	3/8"
DCAR6700-8	1/2"	1/2"	1/2"

(TYPE I) CSA LPG HOSE ASSEMBLIES - STEEL ENDS

Dominion Propane Delivery Hoses are available in 1" I.D. in 100', 125', 150', 175', and 200' lengths.

Dominion Propane Delivery Hoses are CSA-approved assembled used to transport propane gas from a mobile storage tank directly to homes or industries.

Our Delivery Hoses are durable and withstand high-pressure and low-temperature conditions associated with propane transport in commercial, and industrial applications in temperatures ranging from -50°C to +82°C, (-58°F to +180°F).

Made of black nitrile, reinforced by multiple textile layers, and covered with a black chloroprene perforated smooth finish, they are designed to be flexible and resistant to abrasion, weather, and chemical exposure which play a crucial role in safely and efficiently delivering propane gas to its intended destination.


Hose ends are assembled with CSA-approved Male Pipe to Male Pipe Steel Fittings that allow a secure attachment. Each hose assembly is tested and certified to prevent leaks and ensure safety during propane transfer.

SPECIFICATIONS: UL 21, CSA 8.1-2015 (R2020)

* Hose image does not represent actual size.



Part Number	Description	Working Pressure
DS531200-16	1" x 100', MP x MP	Up to 350 P.S.I.
DS531500-16	1" x 125', , MP x MP	
DS531800-16	1" x 150', , MP x MP	
DS532100-16	1" x 175', , MP x MP	
DS532400-16	1" x 200', MP x MP	



Part Number	Max Operating Pressure (P.S.I.)	Temperature Range (°C)	Min. Bending Radius (in)	Weight (lb/ft)
DHPG-16	350	-50 - 82	7.50	0.63

Thermoid®

TYPE I THERMOID POLARFLEX DELIVERY HOSES


Polar Flex/CGA Type 1 is available in 1" I.D. in 100', 125', 150', and 200' lengths with one piece Pro-Sur™ fitting brass coupled assemblies. Pro-Sur fittings are non-sparking, leak resistant, and offer superior coupling retention and a significant reduction in hose replacement costs.

TEMPERATURE RANGE -50F – 180F

Part Number	Description	Working Pressure
DPF531200-16	1" x 100', MP x MP	350 P.S.I.
DPF531500-16	1" x 125', MP x MP	
DPF531800-16	1" x 150', MP x MP	
DPF532100-16	1" x 175', MP x MP	
DPF532400-16	1" x 200', MP x MP	



FLEX CONNECTORS*



Stainless Steel Metal Hose Assemblies for LPG Transfer.
All standard steel and stainless steel fittings and flanges can be supplied to order.
***Special Order: Please Inquire**

HOSE SUPPORT AND RETRACTOR

HANGER ADAPTOR	
Part No.	Description
ME209	1-3/4" M.ACME x 3/8-16" Hanger Adaptor Assembly



MARSHALL BREAK-AWAY COUPLING AND VALVE



ME860S

Part No.	Description
ME860S-6	<i>FloKill</i> 3/4" FNPT x 3/4" FNPT Break-Away - Bracket Style

MARSHALL HOSE END VALVES



DRS

Part No.	Size	Diameter	Length
DRS-12	3/4"	2-11/16"	4-3/16"
DRS-16	1"	3-1/16"	4-3/8"

MARSHALL HOSE END VALVES



ME800



M570

Part No.	Description
ME800	Marshall Excelsior 1-3/4" F. ACME Hose End Valve

FILLER HOSE ADAPTOR

Part Number	Filler Valve Connection Inches	Hose End Valve Connection Inches	Body Material
Brass			
M570	1-3/4" F. Acme	1-3/4" M. Acme	Brass

DRY BREAK TRANSFER SYSTEM



ME806-16



ME86868-16 ASSEMBLED
(FULL PORT GLOBE VALVE
NOT INCLUDED)

Low Emission Transfer Valve			
Part Number	Description	Discharge at Disconnect	Material
ME806-16	Low Emission Transfer Valve 2" FNPT x 3-1/4" F. Acme Swivel Connection	.09 CC	Ductile/Brass



SQUIBB TAYLOR VALVE

FILLER HOSE ADAPTOR

Part Number	Inlet Size	Outlet Connection	Valve Release
DAL-343	1"	1-3/4"	.6 cc


DAL-343



FLEXIBLE GAS PIPING SYSTEM

TracPipe® CounterStrike®
Flexible Gas Piping by OmegaFlex.

Flexible Gas Piping Systems for Commercial, Industrial and Residential



Yellow jacketed TracPipe® CSST and Black jacketed CounterStrike® CSST are compliant with fuel gas codes in all 10 provinces. TracPipe PS-II® CSST is used for Underground gas piping applications. All are available from 3/8" to 2" diameters in long roll lengths.

FLEXIBLE GAS PIPING SYSTEM

CORRUGATED STAINLESS STEEL TUBING WITH POLYETHYLENE JACKET

Part Number	Size (in.)	Pkg. Qty.
SS4-375-250	3/8"	250 ft. coil
SS4-500-250	1/2"	250 ft. coil
SS4-750-250	3/4"	250 ft. coil
SS4-100-180	1"	180 ft. coil



STRAIGHT FITTING - BRASS WITH AUTOFLARE INSERT

Part Number	Size (in.) NPT
FST-375	3/8"
FST-500	1/2"
FSTF-500	1/2" Female
FST-750	3/4"
FST-1000	1"
FST-1250	1-1/4"



TEE FITTING - BRASS WITH AUTOFLARE INSERT

Part Number	Size (in.)
TF500-T500	1/2"
TF750-T750	3/4"



REDUCING TEE FITTING - BRASS

Part Number	Size (in.)
TF-1000-T500	1" x 1" x 1/2"
RT-1001	1" x 3/4" x 1/2"
RT-752	3/4" x 1/2" x 1/2"
TF750-T500	3/4" x 3/4" x 1/2"
RT-1002	1" x 3/4" x 3/4"



COUPLING - BRASS

Part Number	Size (in.)
CPLG-375	3/8"
CPLG-500	1/2"
CPLG-750	3/4"



FLEXIBLE GAS PIPING SYSTEM



90° FLANGE FITTING - BRASS

Part Number	Size (in.)
ELLB-500	1/2"
BF90V-750	3/4"



FLANGE FITTING - BRASS

Part Number	Size (in.)
BFF-500	1/2"

TRACPIPE® PS-II UNDERGROUND GAS PIPING

TracPipe® PS-II is a presleeved gas installation system for underground, rooftop, or exterior wall applications.



TRACPIPE PS-II MALE ADAPTOR


Part Number	Size (in.)
UGF-750	3/4" NPT Male



TRACPIPE PS-II TUBING

Part Number	Size (in.)	Reel Length
UGP-750-250	3/4"	250 ft./reel


TRACPIPE® PS-II UNDERGROUND GAS PIPING



DISTRIBUTION MANIFOLDS

Part Number	Description	Size (in.)
MI-PC	Coated Malleable 4-Port w/Female Ends	3/4" x 1/2" x 1/2" (4)

STAINLESS STEEL GAS CONNECTORS FOR RESIDENTIAL APPLICATIONS



NOTE:

- Configurations come in lengths of 12", 18", 24", 30", 36", 48", 60", & 70". Please inquire about availability.
- Add length as suffix to Part Number: i.e. -12 for 12", -18 for 18", etc. Example: DGC-3131-12 for a 12" connection.

WATER HEATERS, LOGS AND SPACE HEATERS TUBE O.D. 3/8" DIAMETER

Part Number	Description
DGC10-3131	1/2" MPT x 1/2" MPT
DGC10-2131	3/8" MPT x 1/2" MPT
DGC10-2121	3/8" MPT x 3/8" MPT
DGC10-2222	3/8" FPT x 3/8" FPT
DGC10-2122	3/8" MPT x 3/8" FPT
DGC10-3132	1/2" MPT x 1/2" FPT
DGC10-3135	1/2" MPT x 1/2" FPT with Ball Valve
DGC10-2135	3/8" MPT x 1/2" FPT with Ball Valve

RANGES TUBE O.D. 5/8" DIAMETER

Part Number	Description
DGC30-4141	3/4" MPT x 3/4" MPT
DGC30-3141	1/2" MPT x 3/4" MPT
DGC30-3131	1/2" MPT x 1/2" MPT
DGC30-3132	1/2" MPT x 1/2" FPT

ADAPTORS

Part Number	Description
DGCA90-1021	3/8" O.D. x 3/8" MPT Tapped 1/4" FPT
DGCA90-3031	5/8" O.D. x 1/2" MPT Tapped 3/8" FPT
DGCA90-3041	5/8" O.D. x 3/4" MPT Tapped 1/2" FPT
DGCA90-3042	5/8" O.D. x 3/4" FPT

DRYERS TUBE O.D. 1/2" DIAMETER

Part Number	Description
DGC20-3131	1/2" MPT x 1/2" MPT
DGC20-2131	3/8" MPT x 1/2" MPT
DGC20-3122	1/2" MPT x 3/8" FPT
DGC20-3132	1/2" MPT x 1/2" FPT
DGC20-3135	1/2" MPT x 1/2" FPT with Ball Valve
DGC20-2135	3/8" MPT x 1/2" FPT with Ball Valve

SAFETY SHIELD YELLOW COATED STAINLESS STEEL GAS CONNECTORS



DRYERS TUBE O.D. 1/2" DIAMETER

Part Number	Description
20C-3132	1/2" MPT x 1/2" FPT

RANGES TUBE O.D. 5/8" DIAMETER

Part Number	Description
30C-3131-24	1/2" MPT x 1/2" MPT, 24" L
30C-3131-48	1/2" MPT x 1/2" MPT, 48" L
30C-3132-24	1/2" MPT x 1/2" FPT, 24" L
30C-3132-36	1/2" MPT x 1/2" FPT, 36" L
30C-3132-48	1/2" MPT x 1/2" FPT, 48" L
30C-3132-60	1/2" MPT x 1/2" FPT, 60" L

ANTIMICROBIAL BLUE PVC COATED CONNECTORS FOR COMMERCIAL GRADE MOVEABLE EQUIPMENT




Part Number	Description
CAN1650-BP	1/2" ID Available in 36", 48", 60" lengths
CAN1675-BP	3/4" ID Available in 36", 48", 60" lengths
CAN16100BP	1" ID Available in 36", 48" lengths

ANTIMICROBIAL YELLOW PVC COATED CONNECTORS FOR COMMERCIAL GRADE STATIONARY EQUIPMENT



Part Number	Description
CAN1650NPFS48	1/2" ID x 48"

HIGH BTU STAINLESS STEEL GAS CONNECTOR TUBE O.D. 1" DIAMETER



Part Number	Description
40-4142-36	3/4" MPT x 3/4" FPT x 36"

DELUXE SAFETY SYSTEM GAS CONNECTOR KIT



Part Number	Description
CAN1675KITX36	3/4" ID
CAN16100KITX48	1" ID
Available in 36" & 48" lengths	

BALL VALVES



**FULL PORT TWO WAY
BALL VALVE, CGA 3.16,
600 P.S.I.
LONG LEVER HANDLE
FEMALE PIPE TO PIPE**

Part Number	Pipe Size
DBV2103-B-CGA	1/4
DBV2103-C-CGA	3/8
DBV2103-D-CGA	1/2
DBV2103-E-CGA	3/4
DBV2103-F-CGA	1
DBV2103-G-CGA	1-1/4
DBV2103-H-CGA	1-1/2
DBV2103-I-CGA	2



**BALL VALVE, CGA 9.1
APPROVED FOR 1/2 PSIG
TEE HANDLE
FEMALE PIPE TO PIPE**

Part Number	Pipe Size
DBV31-C-CGA	3/8
DBV31-D-CGA	1/2
DBV31-E-CGA	3/4
DBV31-F-CGA	1



**BALL VALVE, CGA 9.1
APPROVED FOR 1/2 PSIG
TEE HANDLE MALE SAE
FLARE TO FEMALE PIPE**

Part Number	Tube	Pipe
DBV5046-6D	3/8	1/2
DBV5046-8D	1/2	1/2



**BALL VALVE, CGA 9.1
APPROVED FOR 1/2 PSIG
TEE HANDLE MALE SAE
FLARE TO FLARE**

Part Number	Pipe
DBV5042-6	3/8
DBV5042-8	1/2
DBV5042-10	5/8



ME831



ME834

**BALL VALVE, 400/600 W.O.G.
NON-SHOCK (WATER, OIL, GAS)
FULL PORT
FEMALE PIPE TO PIPE**

Part Number	W.O.G	Pipe Size
DBV31-B	600	1/4
DBV31-C	600	3/8
DBV31-D	600	1/2
DBV31-E	600	3/4
DBV31-F	600	1
DBV31-G	600	1-1/4
DBV31-H	600	1-1/2
DBV31-I	600	2
DBV31-J	400	2-1/2
DBV31-K	400	3
DBV31-L	400	4



**BALL VALVE, CGA 9.1
APPROVED FOR 1/2 PSIG
TEE HANDLE MALE SAE
FLARE TO MALE PIPE**

Part Number	Tube	Pipe
DBV5048-6D	3/8	1/2
DBV5048-8D	1/2	1/2

NEEDLE VALVES

Part No.	Description	Material
ME831	Needle Valve 1/4" MNPT x 1/4" FNPT	Brass
ME834	Needle Valve 1/4" MNPT x 9/16" -18 LH Male	Brass



QUICK DISCONNECTS

GAS-MATE® COUPLING

One-way shut-off Couplings are designed for LP and natural gas applications where 3/8", 1/2", 3/4" and 1" hose is used. Provide plug-in, plug-out simplicity; no wrenches are needed to connect or disconnect the coupling. When plug is removed from socket, valve shuts off automatically. If there is a rapid temperature rise in appliance or equipment, heat sensitive plug automatically stops the flow of gas.


FOR CONNECTIONS OF GAS COOKING APPLIANCES - AND OTHER GAS-FIRED DEVICES

A.G.A. and C.G.A. design certified for natural gas, manufactured gas, mixed gas, liquefied petroleum LP gas-air mixtures, when the gas application pressure does not exceed 12" water column pressure.



D100-508

Connection	Socket No.	Cap No.	Plug No.	Cap No.
3/8" FNPT	D100-006	D006-CAP	D100-506	D506-CAP
1/2" FNPT	D100-008	-	D100-508	-
3/4" FNPT	D100-010	-	D100-510	-
1" FNPT	D100-012	-	D100-512	-



RV QUICK DISCONNECT SOCKET (WITH BALL VALVE) & PLUG	
Part Number	Description
5LPBV2SF	1/4" Socket with Ball Valve
5LPA12C	1/4" Plug



HIGH PRESSURE GAS QUICK DISCONNECT (250 P.S.I.)	
Part Number	Description
HK-7	1/4" FPT x MPT Socket & Nipple Set

DOMINION PRESSURE GAUGES



J SERIES

DRY PRESSURE GAUGES								
Connection	NPT Connection	Range PSG						
		0-15	0-30	0-60	0-100	0-160	0-200	0-300
Bottom 2" Dial	1/4	J500	J501	J502	J503	J504	J505	J506
Back	1/4	-	-	-	J513	J514	-	-



DP SERIES - STAINLESS STEEL CASING


GLYCERIN FILLED PRESSURE GAUGES							
Connection	NPT Connection	Range PSG					
		0-30	0-60	0-100	0-160	0-200	0-300
Bottom 2-1/2" Dial	1/4	DP802	DP803	DP804	DP805	DP806	DP807
Back 2-1/2" Dial	1/4	-	-	-	DP905	-	-

GLYCERIN FILLED PRESSURE GAUGES								
Connection	NPT Connection	Range PSG						
		0-400	0-600	0-1000	0-1500	0-2000	0-3000	0-5000
Bottom 2-1/2" Dial	1/4	DP817	DP808	DP810	-	DP820	DP830	DP850

SAE 45° FLARE BRASS FITTINGS




FLARE NUT - FORGED LONG STANDARD	
Part Number	Tube Size
D39-4	1/4
D39-5	5/16
D39-6	3/8
D39-8	1/2
D39-10	5/8
D39-12	3/4



FLARE NUT - FORGED SHORT STANDARD REDUCING	
Part Number	Tube Size
D40-6-4	3/8 x 1/4
D40-8-6	1/2 x 3/8
D40-10-8	5/8 x 1/2
D40-12-8	3/4 x 1/2
D40-12-10	3/4 x 5/8



FLARE REDUCING UNION - COUPLING TUBE TO TUBE	
Part Number	Tube Size
D42-4-3	1/4 x 3/16
D42-5-4	5/16 x 1/4
D42-6-4	3/8 x 1/4
D42-6-5	3/8 x 5/16
D42-8-4	1/2 x 1/4
D42-8-6	1/2 x 3/8
D42-10-6	5/8 x 3/8
D42-10-8	5/8 x 1/2
D42-12-8	3/4 x 1/2
D42-12-10	3/4 x 5/8



FLARE NUT - FORGED SHORT STANDARD	
Part Number	Tube Size
D40-3	3/16
D40-4	1/4
D40-5	5/16
D40-6	3/8
D40-8	1/2
D40-10	5/8
D40-12	3/4
D40-14	7/8




FLARE UNION COUPLING - TUBE TO TUBE	
Part Number	Tube Size
D42-2	1/8
D42-3	3/16
D42-4	1/4
D42-5	5/16
D42-6	3/8
D42-8	1/2
D42-10	5/8
D42-12	3/4



FLARE TEE - FORGED TUBE ON 3 ENDS	
Part Number	Tube Size
DF44-4	1/4
DF44-5	5/16
DF44-6	3/8
DF44-8	1/2
DF44-10	5/8

SAE 45° FLARE BRASS FITTINGS



REDUCING TEE - FORGED			
Part Number	Tube Size		
	1	2	3
DF44-6-6-4	3/8 x 3/8 x 1/4		
DF44-6-6-8	3/8 x 3/8 x 1/2		
DF44-8-8-6	1/2 x 1/2 x 3/8		
DF44-8-8-10	1/2 x 1/2 x 5/8		
DF44-10-6-10	5/8 x 3/8 x 5/8		
DF44-10-10-6	5/8 x 5/8 x 3/8		
DF44-10-10-8	5/8 x 5/8 x 1/2		



FLARE TEE - FORGED MALE PIPE ON BRANCH		
Part Number	Size Tube Pipe	
	1	2
DF45-4A	1/4 x 1/8	
DF45-4B	1/4 x 1/4	
DF45-5B	5/16 x 1/4	
DF45-6B	3/8 x 1/4	
DF45-6C	3/8 x 3/8	
DF45-6D	3/8 x 1/2	
DF45-8C	1/2 x 3/8	
DF45-8D	1/2 x 1/2	



FLARE CONNECTOR TUBE TO FEMALE PIPE	
Part Number	Size Tube Pipe
D46-3A	3/16 x 1/8
D46-4A	1/4 x 1/8
D46-4B	1/4 x 1/4
D46-4C	1/4 x 3/8
D46-4D	1/4 x 1/2
D46-5A	5/16 x 1/8
D46-5B	5/16 x 1/4
D46-6A	3/8 x 1/8
D46-6B	3/8 x 1/4
D46-6C	3/8 x 3/8
D46-6D	3/8 x 1/2
D46-6E	3/8 x 3/4
D46-8B	1/2 x 1/4
D46-8C	1/2 x 3/8
D46-8D	1/2 x 1/2
D46-8E	1/2 x 3/4
D46-10C	5/8 x 3/8
D46-10D	5/8 x 1/2
D46-10E	5/8 x 3/4
D46-12D	3/4 x 1/2
D46-12E	3/4 x 3/4



FLARE ADAPTOR MALE FLARE BY FEMALE FLARE TUBE	
Part Number	Tube Size
D47-4-6	1/4 x 1/8
D47-6-4	3/8 x 1/4
D47-6-8	3/8 x 1/2
D47-6-10	3/8 x 5/8
D47-8-6	1/2 x 3/8
D47-8-10	1/2 x 5/8
D47-10-8	5/8 x 1/2
D47-10-12	5/8 x 3/4
D47-12-10	3/4 x 5/8

SAE 45° FLARE BRASS FITTINGS



FLARE CONNECTOR FLARE TUBE TO MALE PIPE	
Part Number	Size Tube Pipe
D48-2A	1/8 x 1/8
D48-3A	3/16 x 1/8
D48-3B	3/16 x 1/4
D48-4A	1/4 x 1/8
D48-4B	1/4 x 1/4
D48-4C	1/4 x 3/8
D48-4D	1/4 x 1/2
D48-5A	5/16 x 1/8
D48-5B	5/16 x 1/4
D48-5C	5/16 x 3/8
D48-6A	3/8 x 1/8
D48-6B	3/8 x 1/4
D48-6C	3/8 x 3/8
D48-6D	3/8 x 1/2
D48-6E	3/8 x 3/4
D48-8B	1/2 x 1/4
D48-8C	1/2 x 3/8
D48-8D	1/2 x 1/2
D48-8E	1/2 x 3/4
D48-10B	5/8 x 1/4
D48-10C	5/8 x 3/8
D48-10D	5/8 x 1/2
D48-10E	5/8 x 3/4
D48-12D	3/4 x 1/2
D48-12E	3/4 x 3/4
D48-14E	7/8 x 3/4
D48-16E	1 x 3/4
D48-16F	1 x 1

FLARE ELBOW 90° - FORGED TUBE TO MALE PIPE	
Part Number	Size Tube Pipe
DF49-2A	1/8 x 1/8
DF49-3B	3/16 x 1/4
DF49-4A	1/4 x 1/8
DF49-4B	1/4 x 1/4
DF49-4C	1/4 x 3/8
DF49-4D	1/4 x 1/2
DF49-5A	5/16 x 1/8
DF49-5B	5/16 x 1/4
DF49-6A	3/8 x 1/8
DF49-6B	3/8 x 1/4
DF49-6C	3/8 x 3/8
DF49-6D	3/8 x 1/2
DF49-6E	3/8 x 3/4
DF49-8B	1/2 x 1/4
DF49-8C	1/2 x 3/8
DF49-8D	1/2 x 1/2
DF49-8E	1/2 x 3/4
DF49-10C	5/8 x 3/8
DF49-10D	5/8 x 1/2
DF49-10E	5/8 x 3/4
DF49-12D	3/4 x 1/2
DF49-12E	3/4 x 3/4

FLARE ELBOW 90° - FORGED TUBE TO FEMALE PIPE	
Part Number	Size Tube Pipe
DF50-4B	1/4 x 1/4
DF50-4C	1/4 x 3/8
DF50-5B	5/16 x 1/4
DF50-6B	3/8 x 1/4
DF50-6C	3/8 x 3/8
DF50-6D	3/8 x 1/2
DF50-6E	3/8 x 3/4
DF50-8C	1/2 x 3/8
DF50-8D	1/2 x 1/2
DF50-8E	1/2 x 3/4
DF50-10C	5/8 x 3/8
DF50-10D	5/8 x 1/2
DF50-10E	5/8 x 3/4

SAE 45° FLARE BRASS FITTINGS



FLARE CROSS - FORGED TUBE FOUR ENDS	
Part Number	Size Tube Pipe
DF52-6	3/8
DF52-8	1/2



FLARE ELBOW 45° - FORGED TUBE TO MALE PIPE	
Part Number	Size Tube Pipe
DF54-4A	1/4 x 1/8
DF54-4B	1/4 x 1/4
DF54-4C	1/4 x 3/8
DF54-5A	5/16 x 1/8
DF54-5B	5/16 x 1/4
DF54-6B	3/8 x 1/4
DF54-6C	3/8 x 3/8
DF54-6D	3/8 x 1/2
DF54-8C	1/2 x 3/8
DF54-8D	1/2 x 1/2
DF54-10C	5/8 x 3/8
DF54-10D	5/8 x 1/2
DF54-12D	3/4 x 1/2
DF54-12E	3/4 x 3/4



FLARE ELBOW 90° - FORGED TUBE TO TUBE	
Part Number	Tube Size
DF55-4	1/4
DF55-5	5/16
DF55-6	3/8
DF55-8	1/2
DF55-10	5/8



FLARE SEALING CAP NUT	
Part Number	Tube Size
D56-3	3/16
D56-4	1/4
D56-5	5/16
D56-6	3/8
D56-8	1/2
D56-10	5/8
D56-12	3/4



FLARE SEALING PLUG	
Part Number	Tube Size
D58-3	3/16
D58-4	1/4
D58-5	5/16
D58-6	3/8
D58-8	1/2
D58-10	5/8
D58-12	3/4



FLARE SEALING BONNET COPPER	
Part Number	Tube Size
D57-4	1/4
D57-5	5/16
D57-6	3/8
D57-8	1/2
D57-10	5/8

BRASS PIPE FITTINGS



MALE PIPE ELBOW 90°	
Part Number	Pipe Size
D99-A	1/8
D99-B	1/4
D99-C	3/8
D99-D	1/2



REDUCING ELBOW 90° - FORGED	
Part Number	Pipe Size
DF100-A	1/8
DF100-B	1/4
DF100-C	3/8
DF100-D	1/2
DF100-E	3/4



MALE PIPE TEE	
Part Number	Pipe Size
DM101-A	1/8
DM101-B	1/4
DM101-C	3/8
DM101-D	1/2
DM101-E	3/4



REDUCING ELBOW 90°	
Part Number	Pipe Size
D99-BA	1/4 x 1/8
D99-CB	3/8 x 1/4
D99-DC	1/2 x 3/8



PIPE TEE - EXTRUDED	
Part Number	Pipe Size
D101-A	1/8
D101-B	1/4
D101-C	3/8
D101-D	1/2
D101-E	3/4



PIPE CROSS - EXTRUDED	
Part Number	Pipe Size
D102-A	1/8
D102-B	1/4
D102-C	3/8
D102-D	1/2



PIPE ELBOW 90° - EXTRUDED	
Part Number	Pipe Size
D100-A	1/8
D100-B	1/4
D100-C	3/8
D100-D	1/2
D100-E	3/4



PIPE TEE - FORGED	
Part Number	Pipe Size
DF101-A	1/8
DF101-B	1/4
DF101-C	3/8
DF101-D	1/2
DF101-E	3/4



PIPE CROSS - FORGED	
Part Number	Pipe Size
DF102-A	1/8
DF102-B	1/4
DF102-D	1/2

BRASS PIPE FITTINGS



PIPE COUPLING	
Part Number	Pipe Size
D103-A	1/8
D103-B	1/4
D103-C	3/8
D103-D	1/2
D103-E	3/4



BRANCH TEE - EXTRUDED MALE ON BRANCH	
Part Number	Pipe Size
D106-A	1/8
D106-B	1/4
D106-C	3/8




STREET TEE - FORGED	
Part Number	Pipe Size
DF107-C	3/8



PIPE UNION	
Part Number	Pipe Size
D104-A	1/8
D104-B	1/4
D104-C	3/8
D104-D	1/2
D104-E	3/4




BRANCH TEE - FORGED MALE ON BRANCH	
Part Number	Pipe Size
DF106-D	1/2



PIPE CAP	
Part Number	Pipe Size
D108-A	1/8
D108-B	1/4
D108-C	3/8
D108-D	1/2
D108-E	3/4



PIPE ELBOW 45° - EXTRUDED	
Part Number	Pipe Size
D105-A	1/8
D105-B	1/4




STREET TEE - EXTRUDED	
Part Number	Pipe Size
D107-A	1/8
D107-B	1/4
D107-C	3/8
D107-D	1/2
D107-E	3/4



SQUARE HEAD PIPE PLUG	
Part Number	Pipe Size
D109-A	1/8
D109-B	1/4
D109-C	3/8
D109-D	1/2
D109-E	3/4
D109-F	1

BRASS PIPE FITTINGS



PIPE BUSHING	
Part Number	Pipe Size
D110-BA	1/4 x 1/8
D110-CA	3/8 x 1/8
D110-CB	3/8 x 1/4
D110-DA	1/2 x 1/8
D110-DB	1/2 x 1/4
D110-DC	1/2 x 3/8
D110-EA	3/4 x 1/8
D110-EB	3/4 x 1/4
D110-EC	3/4 x 3/8
D110-ED	3/4 x 1/2
D110-FB	1 x 1/4
D110-FC	1 x 3/8
D110-FD	1 x 1/2
D110-FE	1 x 3/4



FACE BUSHING	
Part Number	Pipe Size
DFB110-CB	3/8 x 1/4
DFB110-DC	1/2 x 3/8
DFB110-EC	3/4 x 3/8
DFB110-ED	3/4 x 1/2



PIPE LOCK NUT - TAPERED THREAD	
Part Number	Pipe Size
D111-A	1/8
D111-B	1/4
D111-C	3/8
D111-D	1/2
D111-E	3/4



CLOSE NIPPLE YELLOW BRASS	
Part Number	Pipe Size
D112-A	1/8
D112-B	1/4
D112-C	3/8
D112-D	1/2
D112-E	3/4



LONG NIPPLE YELLOW BRASS	
Part Number	Pipe Size
D113-A1 1/2	1/8 x 1-1/2
D113-A2	1/8 x 2
D113-A2 1/2	1/8 x 2-1/2
D113-A3	1/8 x 3
D113-B1 1/2	1/4 x 1-1/2
D113-B2	1/4 x 2
D113-B2 1/2	1/4 x 2-1/2
D113-B3	1/4 x 3
D113-C1 1/2	3/8 x 1-1/2
D113-C2	3/8 x 2
D113-C2 1/2	3/8 x 2-1/2
D113-C3	3/8 x 3
D113-D1 1/2	1/2 x 1-1/2
D113-D2	1/2 x 2
D113-D2 1/2	1/2 x 2-1/2



STREET ELBOW 90° - EXTRUDED	
Part Number	Pipe Size
D115-A	1/8
D115-B	1/4
D115-C	3/8
D115-D	1/2
D115-E	3/4



REDUCING STREET ELBOW	
Part Number	Pipe Size
D115-BA	1/4 x 1/8




STREET ELBOW 90° - FORGED	
Part Number	Pipe Size
D116-A	1/8
D116-B	1/4
D116-C	3/8
D116-CD	3/8 F x 1/2 M
D116-D	1/2
D116-DC	1/2 x 3/8
D116-E	3/4

BRASS PIPE FITTINGS




PIPE PLUG COUNTERSUNK HEX	
Part Number	Pipe Size
D118-A	1/8
D118-B	1/4
D118-C	3/8
D118-D	1/2
D118-E	3/4




PIPE ADAPTOR FEMALE TO MALE	
Part Number	Pipe Size
D120-AA	1/8 x 1/8
D120-BB	1/4 x 1/4
D120-CC	3/8 x 3/8
D120-DD	1/2 x 1/2
D120-EC	3/4 x 3/8
D120-ED	3/4 x 1/2



HEX PIPE NIPPLE	
Part Number	Pipe Size
D122-A	1/8
D122-B	1/4
D122-C	3/8
D122-D	1/2
D122-E	3/4
D122-F	1



PIPE REDUCING COUPLING	
Part Number	Pipe Size
D119-BA	1/4 x 1/8
D119-CA	3/8 x 1/8
D119-CB	3/8 x 1/4
D119-DA	1/2 x 1/8
D119-DB	1/2 x 1/4
D119-DC	1/2 x 3/8
D119-ED	3/4 x 1/2



PIPE ADAPTOR FEMALE TO MALE REDUCING	
Part Number	Pipe Size
D120-BA	1/4 x 1/8
D120-CA	3/8 x 1/8
D120-CB	3/8 x 1/4
D120-DB	1/2 x 1/4
D120-DC	1/2 x 3/8
D120-ED	3/4 x 1/2



HEX PIPE NIPPLE REDUCING	
Part Number	Pipe Size
D122-BA	1/4 x 1/8
D122-CA	3/8 x 1/8
D122-CB	3/8 x 1/4
D122-DB	1/2 x 1/4
D122-DC	1/2 x 3/8
D122-ED	3/4 x 1/2



PIPE PLUG HEX HEAD	
Part Number	Pipe Size
D121-A	1/8
D121-B	1/4
D121-C	3/8
D121-D	1/2
D121-E	3/4
D121-F	1



STREET ELBOW 45°	
Part Number	Pipe Size
D124-A	1/8
D124-B	1/4
D124-C	3/8
D124-D	1/2
D124-E	3/4

WELDING HOSE FITTINGS



HOSE BARB TO WELDING STANDARD 9/16-18 THREAD. RIGHT HAND THREAD - SWIVEL (2 PIECE)	
Part Number	Size Hose I.D.
D132-3R	3/16
D132-4R	1/4
D132-5R	5/16
D132-6R	3/8



HOSE BARB TO WELDING STANDARD 9/16-18 THREAD. LEFT HAND THREAD - SWIVEL (2 PIECE)	
Part Number	Size Hose I.D.
D133-3L	3/16
D133-4L	1/4
D133-5L	5/16
D133-6L	3/8



STRAIGHT BALL SEAT MALE PIPE CONNECTOR TO MALE PIPE TAPERED THREAD	
Part Number	Pipe Size Straight Tapered
D134-AA	1/8 x 1/8
D134-BA	1/4 x 1/8
D134-BB	1/4 x 1/4
D134-CB	3/8 x 1/4
D134-CC	3/8 x 3/8
D134-DC	1/2 x 3/8
D134-DD	1/2 x 1/2
D134-EE	3/4 x 3/4




STANDARD WELDING CONNECTOR 9/16-18 Right hand to Male pipe tapered thread	
Part Number	Pipe Size
D135-RB	1/4
D135-RC	3/8



STANDARD WELDING CONNECTOR 9/16-18 Left hand to Male pipe tapered thread	
Part Number	Pipe Size
D135-LA	1/8
D135-LB	1/4
D135-LC	3/8



WELDING COUPLING STANDARD 9/16-18 BOTH ENDS	
Part Number	Size
D136-R	9/16-18 Right Hand
D136-L	9/16-18 Left Hand



STANDARD WELDING NUTS	
Part Number	Size
D137-R (Oxygen)	9/16-18 Right Hand




STANDARD WELDING NUTS	
Part Number	Size
D137-L (Acetylene)	9/16-18 Left Hand



HOSE BARB FOR USE WITH D137 NUTS	
Part Number	Pipe Size Straight Tapered
D138-3	3/16
D138-4	1/4
D138-5	5/16
D138-6	3/8

INVERTED FLARE FITTINGS



INVERTED FLARE PLUG STEEL	
Part Number	Tube Size
D131-3	3/16
D131-4	1/4
D131-5	5/16
D131-6	3/8



INVERTED FLARE NUT	
BRASS	
Part Number	Tube Size
D141-2	1/8
D141-3	3/16
D141-4	1/4
D141-5	5/16
D141-6	3/8
D141-7	7/16
D141-8	1/2
D141-10	5/8
STEEL	Tube Size
DS141-2	1/8
DS141-3PK	3/16
DS141-4PK	1/4
DS141-5PK	5/16
DS141-6	3/8
DS141-7	7/16
DS141-8	1/2
DS141-12	3/4
LONG NUT STEEL	Tube Size
DSL141-3PK	3/16
DSL141-4PK	1/4
LONG NUT STEEL	Tube Size
DSLJ141-3	10MM x 1.0



INVERTED FLARE UNION	
BRASS	
Part Number	Tube O.D.
D142-2	1/8
D142-3PK	3/16
D142-4PK	1/4
D142-5PK	5/16
D142-6PK	3/8
D142-7	7/16
D142-8	1/2



INVERTED FLARE MALE CONNECTOR	
BRASS	
Part Number	Size Tube Pipe
D148-2A	1/8 x 1/8
D148-3A	3/16 x 1/8
D148-4A	1/4 x 1/8
D148-4B	1/4 x 1/4
D148-5A	5/16 x 1/8
D148-5B	5/16 x 1/4
D148-6A	3/8 x 1/8
D148-6B	3/8 x 1/4
D148-6C	3/8 x 3/8
D148-7B	7/16 x 1/4
D148-8B	1/2 x 1/4
D148-8C	1/2 x 3/8
D148-10D	5/8 x 1/2
D148-12D	3/4 x 1/2


POL FITTINGS



CYLINDER ADAPTOR	
Part Number	Tube O.D.
D1985	1" -20 Male Cylinder Thread x 9/16" -18 LH Male



BRASS CYLINDER ADAPTOR		
Part No.	Inlet	Outlet
D2000	1/4 Inv. Flare	1/4 Male Pipe



POL TEE BLOCKS	
Part Number	Description
D2001-CH	Hardnose, X Flow
D2001-H	Hardnose, Full Flow
D2001-S	Softnose, Full Flow
D2001-SX	Softnose, X Flow



POL NUT	
Part Number	Size
D2002-B	7/8 HEX



POL TAILPIECE ASSEMBLY (1/4 MNPT)	
Part Number	Description
D2002	Softnose, Full Flow
D2002-H	Hardnose, Full Flow
DB2002-H	Body Only



POL TAILPIECE ASSEMBLY (1/4 MNPT) EXCESS FLOW	
Part Number	Description
D2003-T	Softnose



FEMALE POL CAP	
Part Number	Description
D2004	FPOL



MALE POL X MALE SAE ADAPTOR	
Part No.	Description
D2005-6	SOFTNOSE, 3/8 MSAE
D2005-8	SOFTNOSE, 1/2 MSAE
D2005-10	SOFTNOSE, 5/8 MSAE
D2005-6H	HARDNOSE, 3/8 MSAE
D2005-8H	HARDNOSE, 1/2 MSAE
D2005-10H	HARDNOSE, 5/8 MSAE



MALE POL X FEMALE NPT ADAPTOR	
Part No.	Description
D2008-B	SOFTNOSE, 1/4 FNPT



MALE POL PLUG	
Part No.	Description
D2010-H	HARDNOSE, MPOL



FEMALE POL X MALE NPT ADAPTOR	
Part No.	Description
D2011-B	1/4
D2011-D	1/2
D2011-E	3/4

POL FITTINGS



MALE POL X MALE NPT ADAPTOR

Part Number	Description
D2014-B	Softnose, 1/4 MNPT
D2014-CH	Hardnose, 3/8 MNPT
D2014-DH	Hardnose, 1/2 MNPT



- Includes Plastic Strap (Installed)
- Customizing available
- Customer to supply artwork

POL PLUGS (PLASTIC)

Part Number
D2030



POL "O" RING

Part Number
D110



FEMALE POL X FEMALE NPT ADAPTOR

Part Number	FNPT
D2016-B	1/4
D2016-D	1/2



PLASTIC HAND WHEEL

Part Number	Tube O.D.
DHAND WHEEL	Black



MOTOR FUEL ADAPTOR

Part Number	Tube O.D.
D901H	FPOL x 1-3/4 F.ACME



POL TAILPIECE ASSEMBLY WITH O-RING FULL FLOW

Part No.	Thread Size
D2018-L	9/16-18 L.H.



L-POST

Part No.	Description
D8815	Soft Nose POL x 1"-20 Male (4-1/4" long)



POL TAILPIECE ASSEMBLY WITH O-RING EXCESS FLOW C.G.A. APPROVED

Part Number	Thread Size
D2019-L	9/16-18 L.H.

BLACK IRON PIPE NIPPLES



CLOSE NIPPLES			
Schedule 40	Schedule 40 Galvanized	3000 lb. A106 Seamless	Size
DBM112-A	DBMG112-A	DHBM112-A	1/8
DBM112-B	DBMG112-B	DHBM112-B	1/4
DBM112-C	DBMG112-C	DHBM112-C	3/8
DBM112-D	DBMG112-D	DHBM112-D	1/2
DBM112-E	DBMG112-E	DHBM112-E	3/4
DBM112-F	DBMG112-F	DHBM112-F	1
DBM112-G	DBMG112-G	DHBM112-G	1-1/4
DBM112-H	DBMG112-H	DHBM112-H	1-1/2
DBM112-I	DBMG112-I	DHBM112-I	2
DBM112-J	DBMG112-J		2-1/2
DBM112-K	DBMG112-K	DHBM112-K	3
DBM112-L	DBMG112-L		4



LONG NIPPLES			
Schedule 40	Schedule 40 Galvanized	3000 lb. A106 Seamless	Size
DBM113-A1 1/2	DBMG113-A1 1/2	DHBM113-A1 1/2	1/8 x 1-1/2
DBM113-A2	DBMG113-A2	DHBM113-A2	1/8 x 2
DBM113-A2 1/2	DBMG113-A2 1/2	DHBM113-A2 1/2	1/8 x 2-1/2
DBM113-A3	DBMG113-A3	DHBM113-A3	1/8 x 3
DBM113-A3 1/2	DBMG113-A3 1/2	DHBM113-A3 1/2	1/8 x 3-1/2
DBM113-A4	DBMG113-A4	DHBM113-A4	1/8 x 4
DBM113-A4 1/2			1/8 x 4-1/2
DBM113-A5		DHBM113-A5	1/8 x 5
DBM113-A5 1/2		DHBM113-A5 1/2	1/8 x 5-1/2
DBM113-A6	DBMG113-A6	DHBM113-A6	1/8 x 6
DBM113-A7			1/8 x 7
DBM113-A8			1/8 x 8
DBM113-A9			1/8 x 9
DBM113-A10	DBMG113-A10		1/8 x 10
DBM113-A12			1/8 x 12
DBM113-B1 1/2	DBMG113-B1 1/2	DHBM113-B1 1/2	1/4 x 1-1/2
DBM113-B2	DBMG113-B2	DHBM113-B2	1/4 x 2
DBM113-B2 1/2	DBMG113-B2 1/2	DHBM113-B2 1/2	1/4 x 2-1/2
DBM113-B3	DBMG113-B3	DHBM113-B3	1/4 x 3
DBM113-B3 1/2	DBMG113-B3 1/2	DHBM113-B3 1/2	1/4 x 3-1/2
DBM113-B4	DBMG113-B4	DHBM113-B4	1/4 x 4
DBM113-B4 1/2	DBMG113-B4 1/2	DHBM113-B4 1/2	1/4 x 4-1/2
DBM113-B5	DBMG113-B5	DHBM113-B5	1/4 x 5
DBM113-B5 1/2		DHBM113-B5 1/2	1/4 x 5-1/2

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

BLACK IRON PIPE NIPPLES



LONG NIPPLES			
Schedule 40	Schedule 40 Galvanized	3000 lb. A106 Seamless	Size
DBM113-B6	DBMG113-B6	DHBM113-B6	1/4 x 6
DBM113-B7			1/4 x 7
DBM113-B8	DBMG113-B8		1/4 x 8
DBM113-B9	DBMG113-B9		1/4 x 9
DBM113-B10			1/4 x 10
DBM113-B11			1/4 x 11
DBM113-B12	DBMG113-B12		1/4 x 12
DBM113-C1 1/2	DBMG113-C1 1/2	DHBM113-C1 1/2	3/8 x 1-1/2
DBM113-C2	DBMG113-C2	DHBM113-C2	3/8 x 2
DBM113-C2 1/2	DBMG113-C2 1/2	DHBM113-C2 1/2	3/8 x 2-1/2
DBM113-C3	DBMG113-C3	DHBM113-C3	3/8 x 3
DBM113-C3 1/2	DBMG113-C3 1/2		3/8 x 3-1/2
DBM113-C4	DBMG113-C4	DHBM113-C4	3/8 x 4
DBM113-C4 1/2	DBMG113-C4 1/2	DHBM113-C4 1/2	3/8 x 4-1/2
DBM113-C5	DBMG113-C5	DHBM113-C5	3/8 x 5
DBM113-C5 1/2			3/8 x 5-1/2
DBM113-C6	DBMG113-C6	DHBM113-C6	3/8 x 6
DBM113-C7			3/8 x 7
DBM113-C8			3/8 x 8
DBM113-C9			3/8 x 9
DBM113-C10	DBMG113-C10		3/8 x 10
DBM113-C11			3/8 x 11
DBM113-C12	DBMG113-C12		3/8 x 12
DBM113-D1 1/2	DBMG113-D1 1/2	DHBM113-D1 1/2	1/2 x 1-1/2
DBM113-D2	DBMG113-D2	DHBM113-D2	1/2 x 2
DBM113-D2 1/2	DBMG113-D2 1/2	DHBM113-D2 1/2	1/2 x 2-1/2
DBM113-D3	DBMG113-D3	DHBM113-D3	1/2 x 3
DBM113-D3 1/2	DBMG113-D3 1/2	DHBM113-D3 1/2	1/2 x 3-1/2
DBM113-D4	DBMG113-D4	DHBM113-D4	1/2 x 4
DBM113-D4 1/2	DBMG113-D4 1/2	DHBM113-D4 1/2	1/2 x 4-1/2
DBM113-D5	DBMG113-D5	DHBM113-D5	1/2 x 5
DBM113-D5 1/2	DBMG113-D5 1/2	DHBM113-D5 1/2	1/2 x 5-1/2
DBM113-D6	DBMG113-D6	DHBM113-D6	1/2 x 6
DBM113-D7	DBMG113-D7		1/2 x 7
DBM113-D8	DBMG113-D8		1/2 x 8
DBM113-D9			1/2 x 9
DBM113-D10	DBMG113-D10		1/2 x 10
DBM113-D11			1/2 x 11
DBM113-D12	DBMG113-D12		1/2 x 12
DBM113-E1 1/2	DBMG113-E1 1/2	DHBM113-E1 1/2	3/4 x 1-1/2

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

BLACK IRON PIPE NIPPLES



LONG NIPPLES			
Schedule 40	Schedule 40 Galvanized	3000 lb. A106 Seamless	Size
DBM113-E2	DBMG113-E2	DHBM113-E2	3/4 x 2
DBM113-E2 1/2	DBMG113-E2 1/2	DHBM113-E2 1/2	3/4 x 2-1/2
DBM113-E3	DBMG113-E3	DHBM113-E3	3/4 x 3
DBM113-E3 1/2	DBMG113-E3 1/2	DHBM113-E3 1/2	3/4 x 3-1/2
DBM113-E4	DBMG113-E4	DHBM113-E4	3/4 x 4
DBM113-E4 1/2	DBMG113-E4 1/2	DHBM113-E4 1/2	3/4 x 4-1/2
DBM113-E5	DBMG113-E5 1/2	DHBM113-E5	3/4 x 5
DBM113-E5 1/2	DBMG113-E5 1/2	DHBM113-E5 1/2	3/4 x 5-1/2
DBM113-E6	DBMG113-E6	DHBM113-E6	3/4 x 6
DBM113-E7			3/4 x 7
DBM113-E8	DBMG113-E8		3/4 x 8
DBM113-E9			3/4 x 9
DBM113-E10	DBMG113-E10		3/4 x 10
DBM113-E11			3/4 x 11
DBM113-E12	DBMG113-E12		3/4 x 12
DBM113-F2	DBMG113-F2	DHBM113-F2	1 x 2
DBM113-F2 1/2	DBMG113-F2 1/2	DHBM113-F2 1/2	1 x 2-1/2
DBM113-F3	DBMG113-F3	DHBM113-F3	1 x 3
DBM113-F3 1/2	DBMG113-F3 1/2	DHBM113-F3 1/2	1 x 3-1/2
DBM113-F4	DBMG113-F4	DHBM113-F4	1 x 4
DBM113-F4 1/2	DBMG113-F4 1/2	DHBM113-F4 1/2	1 x 4-1/2
DBM113-F5	DBMG113-F5	DHBM113-F5	1 x 5
DBM113-F5 1/2	DBMG113-F5 1/2	DHBM113-F5 1/2	1 x 5-1/2
DBM113-F6	DBMG113-F6	DHBM113-F6	1 x 6
DBM113-F7	DBMG113-F7		1 x 7
DBM113-F8	DBMG113-F8		1 x 8
DBM113-F9			1 x 9
DBM113-F10			1 x 10
DBM113-F11			1 x 11
DBM113-F12	DBMG113-F12		1 x 12
DBM113-G2	DBMG113-G2	DHBM113-G2	1-1/4 x 2
DBM113-G2 1/2	DBMG113-G2 1/2	DHBM113-G2 1/2	1-1/4 x 2-1/2
DBM113-G3	DBMG113-G3	DHBM113-G3	1-1/4 X3
DBM113-G3 1/2	DBMG113-G3 1/2	DHBM113-G3 1/2	1-1/4 x 3-1/2
DBM113-G4	DBMG113-G4	DHBM113-G4	1-1/4 x 4
DBM113-G4 1/2			1-1/4 x 4 -1/2
DBM113-G5	DBMG113-G5	DHBM113-G5	1-1/4 x 5
DBM113-G5 1/2			1-1/4 x 5-1/2
DBM113-G6	DBMG113-G6	DHBM113-G6	1-1/4 x 6
DBM113-G7			1-1/4 x 7

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

Limited stock available. Subject to change without notification.

BLACK IRON PIPE NIPPLES



LONG NIPPLES			
Schedule 40	Schedule 40 Galvanized	3000 lb. A106 Seamless	Size
DBM113-G8	DBMG113-G8		1-1/4 x 8
DBM113-G9			1-1/4 x 9
DBM113-G10			1-1/4 x 10
DBM113-G11	DBMG113-G11		1-1/4 x 11
DBM113-G12			1-1/4 x 12
DBM113-H2	DBMG113-H2	DHBM113-H2	1- 1/2 x 2
DBM113-H2 1/2	DBMG113-H2 1/2	DHBM113-H2 1/2	1-1/2 x 2-1/2
DBM113-H3	DBMG113-H3	DHBM113-H3	1-1/2 x 3
DBM113-H3 1/2	DBMG113-H3 1/2	DHBM113-H3 1/2	1-1/2 x 3-1/2
DBM113-H4	DBMG113-H4	DHBM113-H4	1-1/2 x 4
DBM113-H4 1/2	DBMG113-H4 1/2	DHBM113-H4 1/2	1-1/2 x 4-1/2
DBM113-H5	DBMG113-H5	DHBM113-H5	1-1/2 x 5
DBM113-H5 1/2	DBMG113-H5 1/2	DHBM113-H5 1/2	1-1/2 x 5-1/2
DBM113-H6	DBMG113-H6	DHBM113-H6	1-1/2 x 6
DBM113-H7			1-1/2 x 7
DBM113-H8	DBMG113-H8		1-1/2 x 8
DBM113-H9			1-1/2 x 9
DBM113-H10	DBMG113-H10		1-1/2 x 10
DBM113-H11			1-1/2 x 11
DBM113-H12	DBMG113-H12		1- 1/2 x 12
DBM113-I2 1/2	DBMG113-I2 1/2	DHBM113-I2 1/2	2 x 2-1/2
DBM113-I3	DBMG113-I3	DHBM113-I3	2 x 3
DBM113-I3 1/2	DBMG113-I3 1/2	DHBM113-I3 1/2	2 x 3-1/2
DBM113-I4	DBMG113-I4	DHBM113-I4	2 x 4
DBM113-I4 1/2	DBMG113-I4 1/2	DHBM113-I4 1/2	2 x 4-1/2
DBM113-I5	DBMG113-I5	DHBM113-I5	2 x 5
DBM113-I5 1/2	DBMG113-I5 1/2	DHBM113-I5 1/2	2 x 5-1/2
DBM113-I6	DBMG113-I6	DHBM113-I6	2 x 6
DBM113-I7			2 x 7
DBM113-I8	DBMG113-I8		2 x 8
DBM113-I10			2 x 10
DBM113-I11			2 x 11
DBM113-I12			2 x 12
DBM113-J3	DBMG113-J3		2-1/2 x 3
DBM113-J3 1/2			2-1/2 x 3-1/2
DBM113-J4	DBMG113-J4		2-1/2 x 4
DBM113-J4 1/2			2-1/2 x 4-1/2
DBM113-J5			2-1/2 x 5
DBM113-J6	DBMG113-J6		2-1/2 x 6
DBM113-J8			2-1/2 x 8

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

BLACK IRON PIPE NIPPLES



LONG NIPPLES			
Schedule 40	Schedule 40 Galvanized	3000 lb. A106 Seamless	Size
DBM113-J10			2-1/2 x 10
DBM113-J12			2-1/2 x 12
DBM113-K3	DBMG113-K3		3 x 3
DBM113-K3 1/2			3 x 3-1/2
DBM113-K4	DBMG113-K4		3 x 4
DBM113-K4 1/2			3 x 4-1/2
DBM113-K5	DBMG113-K5		3 x 5
DBM113-K5 1/2			3 x 5 1/2
DBM113-K6	DBMG113-K6		3 x 6
DBM113-K8	DBMG113-K8		3 x 8
DBM113-K10	DBMG113-K10		3 X 10
DBM113K12			3 x 12
DBM113-L4	DBMG113-L4		4 X 4
DBM113-L4 1/2			4 X 4-1/2
DBM113-L5			4 X 5
DBM113-L5 1/2			4 X 5-1/2
DBM113-L6	DBMG113-L6		4 X 6
DBM113-L8			4 X 8
DBM113-L10			4 X 10
DBM113-L12			4 x 12

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



ELBOW 90°				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	3000 lb. A105N Forged	Size
DBM100-A	DBMG100-A			1/8
DBM100-B	DBMG100-B	DHBM100-B		1/4
DBM100-C	DBMG100-C	DHBM100-C	DXBM100-C	3/8
DBM100-D	DBMG100-D	DHBM100-D	DXBM100-D	1/2
DBM100-E	DBMG100-E	DHBM100-E	DXBM100-E	3/4
DBM100-F	DBMG100-F	DHBM100-F	DXBM100-F	1
DBM100-G	DBMG100-G	DHBM100-G		1-1/4
DBM100-H	DBMG100-H	DHBM100-H	DXBM100-H	1-1/2
DBM100-I	DBMG100-I	DHBM100-I	DXBM100-I	2
DBM100-J	DBMG100-J			2-1/2
DBM100-K	DBMG100-K			3
DBM100-L	DBMG100-L			4
DBM100-N	DBMG100-N			6



REDUCING ELBOW 90°			
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	Size
DBM100-BA	DBMG100-BA		1/4 x 1/8
DBM100-CB			3/8 x 1/4
DBM100-DB			1/2 x 1/4
DBM100-DC	DBMG100-DC		1/2 x 3/8
DBM100-EC			3/4 x 3/8
DBM100-ED	DBMG100-ED		3/4 x 1/2
DBM100-FD	DBMG100-FD		1 x 1/2
DBM100-FE	DBMG100-FE		1 x 3/4
DBM100-GD			1-1/4 x 1/2
DBM100-GE	DBMG100-GE		1-1/4 x 3/4
DBM100-GF	DBMG100-GF		1-1/4 x 1
DBM100-HE			1-1/2 x 3/4
DBM100-HF	DBMG100-HF		1-1/2 x 1
DBM100-HG			1-1/2 x 1-1/4
DBM100-ID			2 x 1/2
DBM100-IE			2 x 3/4
DBM100-IF			2 x 1
DBM100-IG			2 x 1-1/4
DBM100-IH	DBMG100-IH		2 x 1-1/2
DBM100-JH			2-1/2 x 1-1/2
DBM100-JI			2-1/2 x 2
DBM100-KI			3 x 2

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



TEE				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	3000 lb. A105N	Size
DBM101-A	DBMG101-A			1/8
DBM101-B	DBMG101-B	DHBM101-B		1/4
DBM101-C	DBMG101-C	DHBM101-C		3/8
DBM101-D	DBMG101-D	DHBM101-D	DXBM101-D	1/2
DBM101-E	DBMG101-E	DHBM101-E	DXBM101-E	3/4
DBM101-F	DBMG101-F	DHBM101-F	DXBM101-F	1
DBM101-G	DBMG101-G	DHBM101-G		1-1/4
DBM101-H	DBMG101-H	DHBM101-H		1-1/2
DBM101-I	DBMG101-I	DHBM101-I		2
DBM101-J	DBMG101-J			2-1/2
DBM101-K	DBMG101-K	DHBM101-K		3
DBM101-L	DBMG101-L			4
DBM101-N				6



REDUCING TEE			
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	Size
DBM101-BA			1/4 x 1/8
DBM101-CB	DBMG101-CB		3/8 x 1/4
DBM101-DB	DBMG101-DB		1/2 x 1/4
DBM101-DC			1/2 x 3/8
DBM101-DE	DBMG101-DE		1/2 x 3/4
DBM101-DF			1/2 x 1
DBM101-EB	DBMG101-EB		3/4 x 1/4
DBM101-EC	DBMG101-EC		3/4 x 3/8
DBM101-ED	DBMG101-ED	DHBM101-ED	3/4 x 1/2
DBM101-EDD	DBMG101-EDD		3/4 x 1/2 x 1/2
DBM101-EDE	DBMG101-EDE		3/4 x 1/2 x 3/4
DBM101-EF			3/4 x 1
DBM101-FD	DBMG101-FD	DHBM101-FD	1 x 1/2
DBM101-FDD			1 x 1/2 x 1/2
DBM101-FDE			1 x 1/2 x 3/4
DBM101-FDF			1 x 1/2 x 1
DBM101-FE		DHBM101-FE	1 x 3/4
DBM101-FED			1 x 3/4 x 1/2
DBM101-FEE			1 x 3/4 x 3/4
DBM101-FEF			1 x 3/4 x 1
DBM101-FG			1 x 1-1/4
DBM101-GD			1-1/4 x 1/2

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



REDUCING TEE			
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	Size
DBM101-GDG			1-1/4 x 1/2 x 1-1/4
DBM101-GE	DBMG101-GE	DHBM101-GE	1-1/4 x 3/4
DBM101-GED			1-1/4 x 3/4 x 1/2
DBM101-GEF			1-1/4 x 3/4 x 1
DBM101-GEG			1-1/4 x 3/4 x 1-1/4
DBM101-GF		DHBM101-GF	1-1/4 x 1
DBM101-GFE			1-1/4 x 1 x 3/4
DBM101-GFF			1-1/4 x 1 x 1
DBM101-HD	DBMG101-HD		1-1/2 x 1/2
DBM101-HE	DBMG101-HE		1-1/2 x 3/4
DBM101-HF	DBMG101-HF	DHBM101-HF	1-1/2 x 1
DBM101-HG		DHBM101-HG	1-1/2 x 1-1/4
DBM101-ID	DBMG101-ID		2 x 1/2
DBM101-IE	DBMG101-IE		2 x 3/4
DBM101-IF	DBMG101-IF	DHBM101-IF	2 x 1
DBM101-IG			2 x 1-1/4
DBM101-IH			2 x 1-1/2
DBM101-KI	DBMG101-KI		3 x 2
DBM101-LI			4 x 2
DBM101-LK			4 x 3



CROSS			
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	3000 lb. A105N	Size
DBM102-B	DBMG102-B		1/4
DBM102-C	DBMG102-C		3/8
DBM102-D	DBMG102-D	DXBM102-D	1/2
DBM102-E	DBMG102-E	DXBM102-E	3/4
DBM102-F	DBMG102-F		1
DBM102-G			1-1/4
DBM102-H			1-1/2
DBM102-I	DBMG102-I		2

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



COUPLING				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	3000 lb. A105N	Size
DBM103-A	DBMG103-A		DXBM103-A	1/8
DBM103-B	DBMG103-B	DHBM103-B	DXBM103-B	1/4
DBM103-C	DBMG103-C	DHBM103-C	DXBM103-C	3/8
DBM103-D	DBMG103-D	DHBM103-D	DXBM103-D	1/2
DBM103-E	DBMG103-E	DHBM103-E	DXBM103-E	3/4
DBM103-F	DBMG103-F	DHBM103-F	DXBM103-F	1
DBM103-G	DBMG103-G	DHBM103-G	DXBM103-G	1-1/4
DBM103-H	DBMG103-H	DHBM103-H	DXBM103-H	1-1/2
DBM103-I	DBMG103-I	DHBM103-I	DXBM103-I	2
DBM103-J	DBMG103-J			2-1/2
DBM103-K	DBMG103-K		DXBM103-K	3
DBM103-L	DBMG103-L			4
DBM103-N				6



STEEL COUPLINGS		
Steel Coupling Schedule 40	Steel Coupling Half Schedule 40	Size
DBMS103-A		1/8
DBMS103-B	DBMSH103-B	1/4
DBMS103-C	DBMSH103-C	3/8
DBMS103-D	DBMSH103-D	1/2
DBMS103-E	DBMSH103-E	3/4
DBMS103-F	DBMSH103-F	1
DBMS103-G	DBMSH103-G	1-1/4
DBMS103-H	DBMSH103-H	1-1/2
DBMS103-I	DBMSH103-I	2
DBMS103-J	DBMSH103-J	2-1/2
DBMS103-K		3
DBMS103-L		4

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



UNION				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	3000 lb. A105N	Size
DBM104-A	DBMG104-A			1/8
DBM104-B	DBMG104-B	DHBM104-B		1/4
DBM104-C	DBMG104-C	DHBM104-C		3/8
DBM104-D	DBMG104-D	DHBM104-D	DXBM104-D	1/2
DBM104-E	DBMG104-E	DHBM104-E	DXBM104-E	3/4
DBM104-F	DBMG104-F	DHBM104-F	DXBM104-F	1
DBM104-G	DBMG104-G	DHBM104-G		1-1/4
DBM104-H	DBMG104-H	DHBM104-H		1-1/2
DBM104-I	DBMG104-I	DHBM104-I		2
DBM104-J	DBMG104-J			2-1/2
DBM104-K	DBMG104-K			3
DBM104-L				4



ELBOW 45°				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	3000 lb. A105N	Size
DBM105-A	DBMG105-A			1/8
DBM105-B	DBMG105-B	DHBM105-B		1/4
DBM105-C	DBMG105-C	DHBM105-C		3/8
DBM105-D	DBMG105-D	DHBM105-D		1/2
DBM105-E	DBMG105-E	DHBM105-E		3/4
DBM105-F	DBMG105-F	DHBM105-F	DXBM105-F	1
DBM105-G	DBMG105-G	DHBM105-G		1-1/4
DBM105-H	DBMG105-H	DHBM105-H		1-1/2
DBM105-I	DBMG105-I	DHBM105-I	DXBM105-I	2
DBM105-J				2-1/2
DBM105-K	DBMG105-K	DHBM105-K		3
DBM105-L	DBMG105-L			4
DBM105-N				6

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



CAP				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	3000 lb. A105N	Size
DBM108-A	DBMG108-A			1/8
DBM108-B	DBMG108-B	DHBM108-B		1/4
DBM108-C	DBMG108-C	DHBM108-C		3/8
DBM108-D	DBMG108-D	DHBM108-D		1/2
DBM108-E	DBMG108-E	DHBM108-E	DXBM108-E	3/4
DBM108-F	DBMG108-F	DHBM108-F	DXBM108-F	1
DBM108-G	DBMG108-G	DHBM108-G		1-1/4
DBM108-H	DBMG108-H	DHBM108-H		1-1/2
DBM108-I	DBMG108-I	DHBM108-I		2
DBM108-J	DBMG108-J			2-1/2
DBM108-K	DBMG108-K			3
DBM108-L				4
DBM108-N				6



PLUG - SQUARE HEAD CORED			
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	3000 lb. A105N	Size
DBM109-A	DBMG109-A	DXBM109-A	1/8
DBM109-B	DBMG109-B	DXBM109-B	1/4
DBM109-C	DBMG109-C	DXBM109-C	3/8
DBM109-D	DBMG109-D	DXBM109-D	1/2
DBM109-E	DBMG109-E	DXBM109-E	3/4
DBM109-F	DBMG109-F	DXBM109-F	1
DBM109-G	DBMG109-G	DXBM109-G	1-1/4
DBM109-H	DBMG109-H	DXBM109-H	1-1/2
DBM109-I	DBMG109-I	DXBM109-I	2
DBM109-J	DBMG109-J		2-1/2
DBM109-K	DBMG109-K		3
DBM109-L			4
DBM109-N			6

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



HEX BUSHING				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	3000 lb. A105N	Wrought Steel	Size
DBM110-BA	DBMG110-BA	DXBM110-BA	DBMS110-BA	1/4 x 1/8
DBM110-CA	DBMG110-CA	DXBM110-CA	DBMS110-CA	3/8 x 1/8
DBM110-CB	DBMG110-CB	DXBM110-CB	DBMS110-CB	3/8 x 1/4
DBM110-DA	DBMG110-DA	DXBM110-DA		1/2 x 1/8
DBM110-DB	DBMG110-DB	DXBM110-DB	DBMS110-DB	1/2 x 1/4
DBM110-DC	DBMG110-DC	DXBM110-DC	DBMS110-DC	1/2 x 3/8
DBM110-EA	DBMG110-EA		DBMS110-EA	3/4 x 1/8
DBM110-EB	DBMG110-EB	DXBM110-EB	DBMS110-EB	3/4 x 1/4
DBM110-EC	DBMG110-EC	DXBM110-EC		3/4 x 3/8
DBM110-ED	DBMG110-ED	DXBM110-ED	DBMS110-ED	3/4 x 1/2
DBM110-FB	DBMG110-FB	DXBM110-FB	DBMS110-FB	1 x 1/4
DBM110-FC	DBMG110-FC		DBMS110-FC	1 x 3/8
DBM110-FD	DBMG110-FD	DXBM110-FD		1 x 1/2
DBM110-FE	DBMG110-FE	DXBM110-FE	DBM110-FE	1 x 3/4
DBM110-GB	DBMG110-GB			1-1/4 x 1/4
DBM110-GC	DBMG110-GC			1-1/4 x 3/8
DBM110-GD	DBMG110-GD	DXBM110-GD		1-1/4 x 1/2
DBM110-GE	DBMG110-GE	DXBM110-GE		1-1/4 x 3/4
DBM110-GF	DBMG110-GF	DXBM110-GF		1-1/4 x 1
DBM110-HB	DBMG110-HB			1-1/2 x 1/4
DBM110-HC	DBMG110-HC			1-1/2 x 3/8
DBM110-HD	DBMG110-HD	DXBM110-HD		1-1/2 x 1/2
DBM110-HE	DBMG110-HE	DXBM110-HE		1-1/2 x 3/4
DBM110-HF		DXBM110-HF		1-1/2 x 1
DBM110-HG	DBMG110-HG	DXBM110-HG		1-1/2 x 1-1/4
	DBMG110-IB			2 x 1/4
DBM110-ID	DBMG110-ID			2 x 1/2
DBM110-IE	DBMG110-IE	DXBM110-IE		2 x 3/4
DBM110-IF	DBMG110-IF			2 x 1
DBM110-IG	DBMG110-IG	DXBM110-IG		2 x 1-1/4
DBM110-IH	DBMG110-IH	DXBM110-IH		2 x 1-1/2
DBM110-JF	DBMG110-JF	DXBM110-JF		2-1/2 x 1
DBM110-JG	DBMG110-JG			2-1/2 x 1-1/4
DBM110-JH	DBMG110-JH			2-1/2 x 1-1/2
DBM110-JI	DBMG110-JI			2-1/2 x 2
DBM110-KF	DBMG110-KF			
DBM110-KG				3 x 1-1/4
DBM110-KH	DBMG110-KH			3 x 1-1/2
DBM110-KI	DBMG110-KI			3 x 2

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



HEX BUSHING				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	3000 lb. A105N	Wrought Steel	Size
DBM110-KJ	DBMG110-KJ			3 x 2-1/2
DBM110-LI	DBMG110-LI			4 x 2
DBM110-LJ				4 x 2-1/2
DBM110-LK	DBMG110-LK			4 x 3
DBM110-NL				6 x 4



LOCKNUT		
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Size
DBM111-D		1/2
DBM111-E	DBMG111-E	3/4
DBM111-F	DBMG111-F	1
DBM111-G	DBMG111-G	1-1/4
DBM111-H	DBMG111-H	1-1/2
	DBMG111-I	2



STREET ELBOW 90°			
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	Size
DBM116-A	DBMG116-A		1/8
DBM116-B	DBMG116-B	DHBM116-B	1/4
DBM116-C	DBMG116-C		3/8
DBM116-D	DBMG116-D		1/2
DBM116-E	DBMG116-E	DHBM116-E	3/4
DBM116-F	DBMG116-F	DHBM116-F	1
DBM116-G	DBMG116-G	DHBM116-G	1-1/4
DBM116-H	DBMG116-H		1-1/2
DBM116-I	DBMG116-I		2
DBM116-J	DBMG116-J		2-1/2
DBM116-K	DBMG116-K		3
DBM116-L			4

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



REDUCING COUPLING				
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Schedule 80 (300#)	3000 lb. A105N	Size
DBM119-BA	DBMG119-BA			1/4 x 1/8
DBM119-CA	DBMG119-CA			3/8 x 1/8
DBM119-CB	DBMG119-CB	DHBM119-CB	DXBM119-CB	3/8 x 1/4
DBM119-DA	DBMG119-DA			1/2 x 1/8
DBM119-DB	DBMG119-DB	DHBM119-DB		1/2 x 1/4
DBM119-DC	DBMG119-DC	DHBM119-DC		1/2 x 3/8
DBM119-EB	DBMG119-EB			3/4 x 1/4
DBM119-EC	DBMG119-EC			3/4 x 3/8
DBM119-ED	DBMG119-ED	DHBM119-ED		3/4 x 1/2
DBM119-FB	DBMG119-FB			1 x 1/4
DBM119-FC	DBMG119-FC			1 x 3/8
DBM119-FD	DBMG119-FD	DHBM119-FD		1 x 1/2
DBM119-FE	DBMG119-FE	DHBM119-FE		1 x 3/4
DBM119-GD	DBMG119-GD			1-1/4 x 1/2
DBM119-GE	DBMG119-GE	DHBM119-GE		1-1/4 x 3/4
DBM119-GF	DBMG119-GF	DHBM119-GF		1-1/4 x 1
DBM119-HD	DBMG119-HD			1-1/2 x 1/2
DBM119-HE	DBMG119-HE	DHBM119-HE		1-1/2 x 3/4
DBM119-HF	DBMG119-HF	DHBM119-HF		1-1/2 x 1
DBM119-HG	DBMG119-HG	DHBM119-HG		1-1/2 x 1-1/4
DBM119-ID	DBMG119-ID			2 x 1/2
DBM119-IE	DBMG119-IE			2 x 3/4
DBM119-IF	DBMG119-IF	DHBM119-IF		2 x 1
DBM119-IG	DBMG119-IG	DHBM119-IG		2 x 1-1/4
DBM119-IH	DBMG119-IH	DHBM119-IH		2 x 1-1/2
DBM119-JF				2-1/2 x 1
DBM119-JG				2-1/2 x 1-1/4
DBM119-JH				2-1/2 x 1-1/2
DBM119-JI	DBMG119-JI	DHBM119-JI		2-1/2 x 2
DBM119-KH				3 x 1-1/2
DBM119-KI	DBMG119-KI			3 x 2
DBM119-KJ	DBMG119-KJ			3 x 2-1/2
DBM119-LI	DBMG119-LI			4 x 2
DBM119-LJ				4 x 2-1/2
DBM119-LK	DBMG119-LK			4 x 3
DBM119-NL				6 x 4

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

MALLEABLE IRON/FORGED PIPE FITTINGS



STREET ELBOW 45°		
Schedule 40 (150#)	Schedule 40 (150#) Galvanized	Size
DBM124-A	DBMG124-A	1/8
DBM124-B	DBMG124-B	1/4
DBM124-C	DBMG124-C	3/8
DBM124-D	DBMG124-D	1/2
DBM124-E	DBMG124-E	3/4
DBM124-F	DBMG124-F	1
DBM124-G	DBMG124-G	1-1/4
DBM124-H	DBMG124-H	1-1/2
DBM124-I	DBMG124-I	2



FLOOR FLANGE	
Schedule 40 (150#)	Size
DBMFF- B	1/4
DBMFF- C	3/8
DBMFF- D	1/2
DBMFF- E	3/4
DBMFF- F	1
DBMFF- G	1-1/4
DBMFF- H	1-1/2
DBMFF-I	2

PIPE SIZE	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
CODE	A	B	C	D	E	F	G	H	I	J	K	L	M	N

TANK AND CYLINDER EQUIPMENT

MULTI-SERVICE VALVES

These multi-service valves are suitable for 100-200 lb DOT containers.



Part No.	Tank Connection	Vapour Service Connection	Filler Connection	Fixed Liquid Level Gauge	DT Length	Propane liquid capacity at various differential pressure (GPM)				Propane Relief Valve Flow Capacity (SCFM) Air		
						10 PSI	25 PSI	50 PSI	100 PSI	PRV Setting	UL	ASME
67.0805	3/4" M.NPT	POL (CGA 510)	1-3/4" ACME	not captive	10.6"	9	15	23	35	375	1123	n/a
67.0808	3/4" M.NPT	POL (CGA 510)	1-3/4" ACME	not captive	11.6"	9	15	23	35	375	1123	n/a



Multi-service valve suitable for ASME tanks where a vapor valve is required. This valve incorporates in the same body a service valve, a vapor withdrawal valve and a fixed level gauge.

Part Number	Tank Connection	Vapour Service Connection	Vapour Line Connection	Gauge Boss	Fixed Liquid Level Gauge	Fixed Level Gauge DT Length	Wrench Hex Flat
67.0720	3/4" M.NPT	Female POL (CGA 510)	1-1/4" M.ACME	1-1/4" F.NPT	Yes	12"	1"

FILLER VALVES

Double back check valve for 420lb tank



66.1122




66.1232

Part No.	Container Connection	Line Connection	Wrench Hex Flat	Propane liquid capacity at various differential pressure (GPM)						
				10 PSI	25 PSI	25 PSI	30 PSI	40 PSI	50 PSI	75 PSI
66.1122	3/4" M.NPT	1-3/4" M.ACME	1-3/4"	17	23	-	28	33	37	-
66.1232	1-1/4" M.NPT	1-3/4" M.ACME	1-3/4"	58	-	98	-	-	146	186

TANK AND CYLINDER EQUIPMENT

INTERNAL PRESSURE RELIEF VALVES FOR ASME AND DOT CONTAINERS

Designed specifically for use as a primary pressure relief device on ASME containers up to 2000 gallon water capacity. Furnished with rain cap for protection against contamination. All these valves have a pre-applied sealant on the container connection. All these valves are ASME approved.



Part Number	Container Connection	Start to Discharge Setting PSI	UL (at 120% of set pressure Flow Capacity SCFM/AIR)	ASME (at 120% of set pressure Flow capacity SCFM/AIR)	Wrench Hex Flat
66.1127*	1" NPT	375	1491	n/a	1-5/16"
66.1129	1" NPT	250	2757	2493	1-3/4"
66.1130	1-1/4" NPT	250	4312	3913	2-1/4"
66.1135 (Fully Internal)	1" NPT	250	864	786	1-5/16"

*For a 420lb tank

RAIN CAPS FOR INTERNAL PRESSURE RELIEF VALVES	
Part Number	Description
ST85	Small
ST85-L	Large

TANK AND CYLINDER EQUIPMENT

SERVICE VALVES FOR DOT FORK LIFT AND ASME MOTOR FUEL CONTAINERS



80.2064



80.2146

Part Number	Container Connection	Outlet Connection	Normal Application	Excess Flow Closing
80.2146	3/4" M.NGT	POL (CGA 510)	ASME Motor Fuel	1.5 GPM
80.2064*		3/8" 18 NPT	DOT Fork Lift	2.6 GPM

*For a 33-1/3 cylinder

FIXED LIQUID LEVEL GAUGES



Part Number	Container Connection	DT Length
66.1072	1/4" M.NGT	12"
66.1120	1/4" M.NPT	5.6"
66.1124	1/4" M.NPT	Without

INTERNAL PRESSURE RELIEF VALVE FOR DOT FORK LIFT CYLINDERS



66.0248

Part Number	Container Connection	Start to Discharge Setting PSI	UL (at 120% of set pressure) Flow capacity SCFM/AIR	Wrench Hex Flat
66.0248	3/4" NPT	375	400	1-1/16"

TANK AND CYLINDER EQUIPMENT

FORKLIFT ACME CONNECTORS



M220M

MALE ACME X MALE NPT ADAPTORS			
Part Number	Intel Connection	Outlet	Application
M220M	3/8" FNPT	1-1/4" M ACME	Service Valve
M220F	1-1/4" F ACME	1/4" FNPT	Fuel Line



M220F

REPLACEMENT PARTS	
Part Number	
RI140007	O-Ring
RI14101014	Flat Washer

LIQUID WATHDRAWAL VALVES WITH EXCESS FLOW

All these valves are designed for liquid withdrawal from stationary containers.



69.0010



66.1109

LIQUID WITHDRAWAL ADAPTORS	
Part Number	Description
ME458	1-5/8" -12 UN Inlet x 3/4" FNPT Outlet ... Fits All New UL Listed Valves
ME458-03	Replacement 6/6 Nylon Gasket for ME453, ME455 and ME458
ME458-04	Replacement Nitrile/ Buna O-Ring for ME458

SERVICE VALVE FOR ASME AND DOT CONTAINERS OR FUEL APPLICATION



Part Number	Tank Connection	Vapour Service Connection	Fixed Liquid Level Gauge	Fixed Level Gauge DT Length
80.3135*	3/4" NGT	POL CGA 510	Not captive	11.1"

*For a 420lb tank

TANK AND CYLINDER EQUIPMENT

SERVICE VALVES FOR DOT CYLINDERS



80.6032



LPG-100LB



PVE3250CLM116

Part Number	Cylinder Connection	Outlet Connection	Normal Application	Liquid Level Gauge	DT Length	Relief Setting	UL rated discharge flow capacity (SCFM)
80.6032	3/4" NPT	Female POL (CGA 510)	DOT cylinder up to 200 lbs	Yes	10.6"	375	765
LPG-100LB			Service valve on DOT cylinder	Yes			n/a
PVE3250CLM116	3/4" MNGT	Male CGA555	DOT cylinder up to 100 lbs	-	11.6	375	1.0 GPM/LPG

TYPE 1 ACME CYLINDER VALVE WITH OVERFILL PROTECTION DEVICE (OPD)

Part Number	Cylinder Capacity	Container Connection	Container Connection	Relief Setting	Dip Tube
OPD-5LB	5 lbs	3/4" - 14 NGT	Type 1 ACME and POL	375 PSIG	3.0"
OPD-10LB	10 lbs	3/4" - 14 NGT	Type 1 ACME and POL	375 PSIG	3.6"
OPD-20LB	20 lbs	3/4" - 14 NGT	Type 1 ACME and POL	375 PSIG	4.0"
OPD-30LB	30 lbs	3/4" - 14 NGT	Type 1 ACME and POL	375 PSIG	4.8"
OPD-40LB	40 lbs	3/4" - 14 NGT	Type 1 ACME and POL	375 PSIG	6.5"

DUST CAP
Part Number
OPD-CAP



OPD-20LB



OPD-40LB

TANK AND CYLINDER EQUIPMENT

LPG FLOAT GAUGES, FLANGED FOUR BOLT MODEL



Part Number	Nominal Ø Inches	Diameter Ø Inches	Tank Type	Container Gallons	Capacity Litres	Diameter (mm)	
						A	B
2071.U	37"	939,80	horizontal	500	1,892.70	510	438
487-989-1-011	41"	1.041,40	horizontal	1000	3,785.40	553	477

LPG THREADED FLOAT GAUGES



Part Number	Nominal Ø Inches	Diameter Ø Inches	Tank Type	Container Gallons	Capacity Litres	Diameter (mm)		Container Connection
						A	B	
2071.U1	37"	939.80	horizontal	500	1,892.70	510	438	1"
2072.U1	41"	1,041,40	horizontal	1000	3,785.40	553	477	1"

FISHER™

CYLINDER FILLING VALVE

N201 fills DOT cylinders by weight and stops the gas supply when specified fill weight is reached. Operated by air pressure, it is designed for beam type scales and requires no electrical or mechanical power.

The assembly comes completely piped up and includes special parts that allow the slide weight on the scale to move to zero. A red button appears in the indicator on top of the N201 each time a cylinder is filled to the desired weight.



N201

TORCH KITS



TORCH KITS			
Part Number	Description	w/ MEGR-6120-30	w/ DFT-445
DTK21EF-10W	10 FT Hose Kit	DTK21EF-10WM	DTK-445-KIT10
DTK21EF-15W	15 FT Hose Kit	DTK21EF-15WM	DTK-445-KIT15
DTK21EF-20W	20 FT Hose Kit	DTK21EF-20WM	DTK-445-KIT20
DTK21EF-25W	25 FT Hose Kit	-	DTK-445-KIT25
DTK21EF-30W	30 FT Hose Kit	-	DTK-445-KIT30

TORCH HEADS	
Part Number	Description
DFT-250W	220,000 BTU
TP-VALVE	TORCH VALVE
DFT-445	45° HEAD HOSE

ADJUSTABLE CONFIGURATION	
Part Number	Description
MEGR-6120-30	High Pressure Adjustable Reg 1-30 PSI - 1/4" FNPT Inlet/Outlet



HOSE ASSEMBLIES	
Part Number	Description
D34120-4	10 FT
D34180-4	15 FT
D34240-4	20 FT
D34300-4	25 FT
D34360-4	30 FT

FISHER REGULATORS	
Part Number	Description
67CH-743	W/O FITTINGS
67CH-743-1	W/FITTINGS
67CH-743(PLL)	Use with Flagro FT6-7, FT6-5



VT3-30C



VT2-23C

VT3-30C - RED DRAGON

- 500,000 BTU Torch
- c/w flame adjusting needle valve, 10' hose, POL fitting & spark lighter

VT2-23C - WEED DRAGON

- 100,000 BTU Torch
- c/w needle valve, 10' hose, regulator, hand-wheel, POLX & spark lighter



**CD-100
TORCH KIT
& CYLINDER
NOT INCLUDED**

TORCHES AND BURNERS

HANDLES

Ergonomical design, made of impact-proof, heat-resistant plastic and brass valve. Euro safety-handles, a new generation with integrated light-weight economizer valve.



SE3403




SE3407

EXTENSION TUBES

Extension tubes made of chromium plated steel. Extension tubes, are suitable for all handles and burners, and bend 40°.

- SE3710** (10cm) (approx. 4")
- SE3720** (20cm) (approx. 8")
- SE3735** (35cm) (approx. 14")
- SE3760** (60cm) (approx. 24")



ACCESSORIES

Part Number	Description
SE252090116	Support Stand
SE2110600	Pilot Knob Repair Set
SE2110500	Main Pressing Pin Repair Set
SE2111200	Lower Pressing Pin Repair Set

BURNERS

Standard types, made of surface treated brass or chromium plated steel alloy, all with inlet-socket M 20x1.
Special types, made of chromium plated steel, all with inlet socket M 20x1.

Suitable for extension tubes and combihandles.



- | | |
|----------------------------|--|
| SE3122 (13,115 BTU) | Burners for precision electrical work, hard and soft soldering etc. made of brass. |
| SE3128 (19,670 BTU) | |



- | | |
|----------------------------|--|
| SE3132 (30,565 BTU) | Burners for flooring, industrial soldering and plumbing etc., made of brass. |
| SE3135 (70,010 BTU) | |



- | | |
|-----------------------------|--|
| SE3145 (109,280 BTU) | Burners for roofing, road work, preheating and built-in devices etc., made of special chromium plated steel alloy. |
| SE3151 (165,970 BTU) | |
| SE3157 (240,250 BTU) | |
| SE3163 (292,670 BTU) | |



- | | |
|-----------------------------|--|
| SE9251 (153,000 BTU) | Burners, special wind protected for roofing, road work etc. made of chromium plated steel alloy. |
| SE9257 (209,690 BTU) | |

PROPANE HEATERS AND GAS LIGHTS



HS35LP



HS125NG



PROPANE FORCED AIR HEATERS

Part Number	BTU Rating
HS125FAV	35,000

PROPANE RADIANT HEATERS

Part Number	BTU Rating
HS35LP	35,000
HS125NG	125,000

PROPANE CONVECTION HEATERS

Part Number	BTU Rating
HS200CV	200,000



MH15T



MH30T

TANK TOP HEATERS

Part Number	BTU Rating
MH15T (Single)	14,000
MH30T (Double)	26,000
20 LB - Stand	Stand for 20 LB Propane Tank

PARTS LIST

Part No.	Description
11663	Regulator (HS35LP Models)
20338	Burner Nose
20339	Replacement Seal
20735	Piezo
23531	Ignitor (HS35LP)
F273606	Regulator (MH12T)
F273699	Fuel Filter (Buddy)
F271803	12" Hose Ass'y w/ Regulator for MH188

PROPANE GAS LIGHTS

Part Number	BTU Rating
MHGLLPB (Brass)	70 W
MHGLLPG (Gray)	70 W



MH18B

"BUDDY" PORTABLE HEATERS

Part Number	BTU Rating
MH18B	18,000

TORCHES AND LIQUID BURNERS

VAPOUR TORCHES



Part Number	BTU Rating
FT-100	25,000 - 80,000
FT-250	90,000 - 300,000
FT-500	110,000 - 410,000

TORCHES EQUIPPED WITH 100% SAFETY SHUT-OFF SYSTEM



Part Number	BTU Rating
FT-100 SV	25,000 - 80,000
FT-250 SV	90,000 - 300,000
FT-500 SV	110,000 - 410,000

LIQUID TORCHES



Part Number	BTU Rating
FT6-3	300,000
FT6-5	500,000
FT6-7	700,000
FT6-9	900,000
FT8-10	1,000,000
FT8-15	1,500,000
FT8-20	2,000,000




Part Number	BTU Rating
N100	Torch Needle Valve

STRAIGHT LIQUID BURNERS



Part Number	BTU Rating
FT1-5	500,000
FT1-7	700,000
FT4-10	1,000,000
FT4-15	1,500,000
FT4-20	2,000,000

WELL TYPE LIQUID BURNERS



Part Number	BTU Rating
FT2-3	300,000
FT2-5	500,000
FT2-7	700,000
FT5-10	1,000,000
FT5-15	1,500,000
FT5-20	2,000,000

TORCHES AND LIQUID BURNERS

F-150 HEAT CANNON

Temporary heat for use during construction and maintenance



SPECIFICATIONS

MODEL F-150
HOSE LENGTH 20 feet standard
REGULATOR WITH POL Adjustable to 20 PSI max.
APPROVED ULC Listed

- Adjustable heat from 50,000 to 150,000 BTU/HR

FLAGRO CONSTRUCTION HEATERS

F-400 HEAT CANNON

Dual Fuel Heater
Propane or Natural Gas Fired



SPECIFICATIONS

MODEL F-400T
INPUT 400,000 BTU/HR
Natural Gas or Propane
APPROVED ULC Listed

CONSTRUCTION HEATERS

INDIRECT FIRED HEATERS



FVP-400



FVP-400
WITH OPTIONAL FV-HD12
FLEXIBLE DUCTING



PART NO: FV-HD12
12 INCH X 15FT
FLEXIBLE DUCTING

SPECIFICATIONS

MODEL FVP-400
INPUT 395,000 BTU/HR
IGNITION Direct Spark Ignition

- Indirect fired - heat exchanger allows for external exhaust of combustion products
- Thermostatically controlled
- Heavy duty pneumatic tires and slim design provides for easy site mobility and slim design provides for easy site mobility and transportation
- FVO-400 model has built-in fuel tank
- Your choice of heating oil, diesel, kerosene, propane or natural gas
- Warnock-Hersev approved

RV AND CAMPING REGULATORS

SINGLE-STAGE 90° REGULATOR ASSEMBLY

With QCC Nut Inlet; 100,000 BTU



Part Number	Description
BBQREG/HA-22	5/16" x 22" 3/8" F.SAE Swivel

SINGLE-STAGE REGULATOR

With Drip Lip Vent; 140,000 BTU



Part Number	Description
MG230-00	1/4" FNPT x 3/8" FNPT

SINGLE-STAGE REGULATOR

MG230-00 with Full Flow Handwheel
POL; 140,000 BTU



Part Number	Description
MG230#20383	MPOL x 3/8" FNPT

TWO-STAGE REGULATOR

With 6:00 Vent; 160,000 BTU



Part Number	Inlet x Outlet
MG290-00	1/4" FNPT x 3/8" FNPT

TWO-STAGE REGULATOR

MG290-00 with 9:00 Vent 160,000 BTU



Part Number	Inlet and Outlet
MG299-00	1/4" FNPT x 3/8" FNPT

TWO-STAGE REGULATOR

MG299-00 with Excess Flow
POL 160,000 BTU



Part Number	Description
MG294-00	MPOL x 3/8" FNP

AUTOMATIC CHANGEOVER REGULATOR

210,000 BTU



Part Number	Description
MG254-00	1/4" FEM.INV.FLARE x 3/8" FNPT

SINGLE-STAGE REGULATOR



Part Number	Description
MG224-00	MG230-00 with Full Flow POL

Z MOUNTING BRACKET



Part Number
MG240-32

REGULATOR COVER

For Second Stage of MG254
and MG290



Part Number
MG862-00

PROPANE CONNECTORS

TYPE 1 "TEE-FOR-TWO"



Part Number	Hose and Hose End
MBG-412	1-5/16" F.ACME x 1" - 20M x 1" - 20M

ADAPTOR



Part Number	Hose and Hose End
MBG-488	1" x 20F x 1/4" MPT

"EXTEND-A-FLOW" TEE



Part No.	Hose and Hose End
MBG-415	MPOL x FPOL x 1" - 20M

"SECOND CHANCE" ADAPTOR

Allows for use of small disposable LP cylinders as a back-up supply
Made with MBG-1899 & MBG-487



Part No.	Hose and Hose End
MBG-480	MPOLX x 1-5/16" ACME x 1" - 20M

ADAPTOR WITH CHECK VALVE



Part No.	Hose and Hose End
MBG-493	9/16" 18L x 1" - 20M

"EXTEND-A-STAY" TEE



Part No.	Hose and Hose End
MBG-420	MPOL x FPOL x 1" - 20M x w/1/4" INV. FL.

"CAP-A-TEE"



Part No.	Hose and Hose End
MBG-483	Fits 1" - 20M Branch

RETRO-Q CYLINDER VALVE ADAPTOR




Part No.	Description
MBG-1899	M.POL x M.QCC1

"EXTEND-A-FLOW PLUS"



Part No.	Hose and Hose End
MBG-423	MPOLX x 1-5/16" ACME x 1" - 20M

"RESERVE GAS" ADAPTOR



Part No.	Hose and Hose End
MBG-487	1" - 20F - Female POL

FEMALE QCC NUT



Part No.	Description	Colour
MBG-1851-A02	Excess Flow: 120,000 BTU	Black
MBG-1851-A03	Excess Flow: 200,000 BTU	Green

PROPANE CONNECTORS

PRIMUS ADAPTOR ASSEMBLY



Part Number	Description
MBG-491	3/8" M. Flare x 1" - 20 Male

PRIMUS ADAPTOR ASSEMBLY



Part Number	Description
MBG-492	1" - 20 Male x 1/4" FNPT

CAMP-APPLIANCE HOOK-UPS



MBG-423

CAMP-APPLIANCE TAP-IN KIT M.POL X M.QCC X M. PRIMUS W/MBG-423	
Part Number	Hose Size
D538-144-4	1/4" x 12' (D40144-4)



TWO CAMP-APPLIANCE HOOK-UP F.PRIMUS X M.PRIMUS X M.PRIMUS W/MBG-488		
Part Number	Hose	Run Hose
D4141824-4	1/4" x 18"	1/4" x 2'
D4141836-4	1/4" x 18"	1/4" x 3'
D41418120-4	1/4 x 18"	1/4" x 10'
D41418144-4	1/4 x 18"	1/4" x 12'
D4142424-4	1/4" x 2'	1/4" x 2'
D4142436-4	1/4" x 2'	1/4" x 3'
D41424120-4	1/4" x 2'	1/4" x 10'
D41424144-4	1/4" x 2'	1/4" x 12'

ADAPTOR



1/4" MALE PIPE X 1/4" FEMALE PIPE WITH RV QUICK DISCONNECT

Part No.	Length
D2472-4QCS	6'
D24120-4QCS	10'
D24144-4QCS	12'
D24180-4QCS	15'

1/4" FEMALE PIPE BOTH ENDS

Part No.	Length
D7736-4	3'
D77144-4	12'



D77144-4 WITH M1-20 MALE PRIMUS X RV QUICK DISCONNECT PLUG ENDS

Part No.	Length
D91144-4LPA	12'

1/4" MALE x 1/4" FEMALE PIPE WITH MALE TEE 2X RV QUICK DISCONNECT SOCKETS AND 1X RV QUICK DISCONNECT PLUG

Part No.	Length
D54936-4QD	3'

OTHER LENGTHS AVAILABLE

RV QUICK DISCONNECT SOCKET (WITH BALL VALVE) AND PLUG



Part Number	Description
5LPBV2SF	1/4" Socket with Ball Valve
5LPA12C	1/4" Plug

GAS OUTLET BOXES



Why Fill Up When You Can Hook Up?



PVC GAS OUTLET BOX



Part Number	Description	Inlet Size
BBQ-4GNS	Grey	3/8
BBQ-4WNS	White	3/8
BBQ-4GNS-50	Grey	1/2
BBQ-4WNS-50	White	1/2

- Low pressure gas connection
- Available in white or grey UV rated PVC surface mount box
- CGA / AGA approved indoor/outdoor use
- 60 Mbtu NG / 90 Mbtu LP
- Rear or bottom connection
- 3/8" or 1/2" NPT pipe connection
- 3/8" or 1/2" Quick disconnect plug included
- Dimensions: 6-7/8" x 5-3/8" x 3"
- Temperature Ratings: Approved to -40 degrees C

DOUBLE STAINLESS STEEL GAS OUTLET BOX



Part Number
BBQ-DBL-SS

- Low pressure gas connection
- Stainless steel surface mount box
- CGA / AGA approved indoor/outdoor use
- 60 Mbtu NG / 90 Mbtu LP
- Rear or bottom connection
- 1/2" NPT pipe connection
- 3/8" Quick disconnect plug included
- Dimensions: 7" x 5-1/4" x 2-3/8"
- Temperature Ratings: Approved to -40 degrees C



STAINLESS STEEL GAS OUTLET BOX



Part Number
BBQ-SSSM

- Low pressure gas connection
- Stainless steel surface mount box
- CGA / AGA approved indoor/outdoor use
- 60 Mbtu NG / 90 Mbtu LP
- Rear or bottom connection
- 3/8" NPT pipe connection
- 3/8" Quick disconnect plug included
- Dimensions: 7" x 5-1/4" x 2-3/8"
- Temperature Ratings: Approved to -40 degrees C



Part Number
BBQ-SS-50

- Stainless steel surface mount box
- 1/2" NPT inlet connection
- 1/2" Quick disconnect outlet
- 90M BTU natural gas
- 138M BTU LP
- Dimensions: 7" x 5-1/4" x 2-3/8"
- Temperature Ratings: Approved to -40 degrees C



THREAD SEALANTS, LEAK DETECTOR AND TEFLON TAPE

MASTERS METALLIC COMPOUND

Part Number	Container	Net Contents	Quantity Per Case
DCP250BT	250 ml. (approx. 1/2 pt.) Brush Top	850 g	25



MASTERS PRO-DOPE

Part Number	Container	Net Contents	Quantity Per Case
DPD250BT	250 ml. (approx. 1/2 pt.) Brush Top	340 g	25



MASTERS LEAK DETECTOR

Part No.	Container	Net Contents	Quantity Per Case
DLD-227	227 ml. (approx. 8 oz.) Applicator Bottle	227 ml	20
DLD-4L	4 Litre (approx. 1 gal.) Bottle	4 Litres	4
DLD-20L	20 Litre (approx. 5 gal.) Pail	20 Litres	1



YELLOW TAPE FOR GAS LINES

Part No.	Width	Length
904-128	1/2"	240"
904-1212	3/4"	255"

WHITE TEFLON TAPE

Part No.	Width	Length
904-108	1/2"	480"
D121-M12	3/4"	240"
D121-M16	1"	240"

PINK TEFLON TAPE

Part No.	Width	Length
D121-M8 PINK	1/2"	480"

TUBE STRAPS

TUBE STRAPS

Two Hole Steel Copper Coated



Part Number	Tube Size O.D.
D14-8	1/2
D14-10	5/8
D14-14	7/8
D14-18	1-1/8
D14-22	1-3/8

TUBE STRAPS

Closed Steel Zinc Plated
EPDM Rubber Cushioned
3/8" Hole, 5/8" Band



Part Number	Tube Size O.D.
D16-4	1/4
D16-5	5/16
D16-6	3/8
D16-8	1/2
D16-10	5/8
D16-12	3/4
D16-14	7/8
D16-16	1
D16-18	1-1/8
D16-20	1-1/4
D16-24	1-1/2
D16-32	2
D16-40	2-1/2
D16-48	3
D16-64	4

TUBE STRAPS

Closed Steel Zinc Plated
EPDM Rubber Cushioned
1/4" Hole, 1/2" Band



Part Number	Tube Size O.D.
D17-4	1/4
D17-5	5/16
D17-6	3/8
D17-8	1/2
D17-10	5/8
D17-12	3/4
D17-14	7/8
D17-16	1
D17-18	1-1/8
D17-20	1-1/4
D17-24	1-1/2
D17-28	1-3/4
D17-32	2
D17-38	2-3/8
D17-40	2-1/2
D17-48	3
D17-56	3-1/2
D17-64	4

TUBE STRAPS "DUPLEX"

Two Tubes Steel Zinc Plated



Part Number	Tube Size O.D.
D19-44	1/4 1/4
D19-66	3/8 3/8

TUBE STRAPS

One Hole Steel Zinc Plated Heavy Type



Part Number	Tube Size O.D.
D20-2	1/8
D20-3	3/16
D20-4	1/4
D20-5	5/16
D20-6	3/8
D20-8	1/2
D20-10	5/8
D20-12	3/4
D20-16	1
D20-20	1-1/4

TUBE STRAPS

One Hole Everdur Copper Alloy Type




Part No.	Tube O.D.	No. of Tubes
D21-4	1/4	1/2

NOTES


[illegible]

DIMENSIONAL STANDARDS

Actual Outside Diameters of Pipe Threads



Actual Outside Diameters of Tubing



TUBE FITTING SIZE AND THREAD STANDARDS

O.D. Tube Size	Compression		S.A.E. Flare		J.I.C. Flare		Inv. Flare		Threaded Sleeve	
	O.D.	Thread	O.D.	Thread	O.D.	Thread	O.D.	Thread	O.D.	Thread
1/8	5/16	24	5/16	24	5/16	24	5/16	28	5/16	24
3/16	3/8	24	3/8	24	3/8	24	3/8	24	3/8	24
1/4	7/16	24	7/16	20	7/16	20	7/16	24	7/16	24
5/16	1/2	24	1/2	20	1/2	20	1/2	20	1/2	20
3/8	9/16	24	5/8	18	9/16	18	5/8	18	9/16	20
7/16	5/8	24	11/16	16	-	-	11/16	18	5/8	18
1/2	11/16	20	3/4	16	3/4	16	3/4	18	11/16	16
5/8	13/16	18	7/8	14	7/8	14	7/8	18	-	-
3/4	1	18	1-1/16	14	1-1/16	12	1-1/16	16	-	-
7/8	1-1/8	18	1-1/4	12	1-3/16	12	1-3/16	16	-	-
1	1-1/4	18	1-3/8	12	1-5/16	12	1-5/16	16	-	-
1-1/4	-	-	-	-	1-5/8	12	-	-	-	-
1-1/2	-	-	-	-	1-7/8	12	-	-	-	-
2	-	-	-	-	2-1/2	12	-	-	-	-

FRACTIONAL SIZE CODE used with all Part Numbers to designate Tube and Pipe Fractional Sizes.

Tube Size Code - 1/16THS	1/8	3/16	1/4	5/16	3/8	7/16	1/2	5/8	3/4	7/8	1	1-1/4	1-1/2	2
	2	3	4	5	6	7	8	10	12	14	16	20	24	32
Pipe Size Code	1/8	1/4	3/8	1/2	3/4	1	1-1/4	1-1/2	2	2-1/2	3	4	5	6
	A	B	C	D	E	F	G	H	I	J	K	L	M	N

WARNING!

FAILURE, IMPROPER SELECTION OR IMPROPER USE OF THE PRODUCTS AND/OR SYSTEMS OR RELATED ITEMS DESCRIBED HEREIN CAN CAUSE PROPERTY DAMAGE, PERSONAL INJURY AND DEATH.

This catalogue and other information from Dominion Fittings and The Hillman Group Canada ULC provide product and/or system options for further investigation by users possessing technical expertise. It is imperative that all aspects of the application be determined and a thorough review of the information concerning the products in this catalogue be undertaken. Due to the various operating conditions and applications for these products or systems, the installer or user, by means of its own analysis and testing, is solely responsible for making the final selection of the products and systems and will assure all performance, safety and warning requirements are adhered to or met.

The products described herein, including without limitation, product features, specifications, designs, availability and pricing, are subject to change by Dominion Fittings at any time without notice. The information and drawings in this catalogue are the exclusive property of Dominion Fittings and may not be reproduced without written consent from the company. The items described in this document are hereby offered for sale by The Hillman Group Canada.



TORONTO

900 Passmore Avenue, Toronto, ON, M1X 0C6

Tel: 416-694-3351

Fax: 416-981-7956

LAVAL

2591 Debray Street Laval, QC H7S 2J4

Tel: 1-450-688-4292

Fax: 1-450-688-4750

EDMONTON

17306 129th Avenue Edmonton, AB T5V 0C7

Tel: 1-800-262-9026

Fax: 1-780-900-0463

WINNIPEG

1670-A Inkster Blvd. Winnipeg, MB. R2X 2W8

Tel: 1-204 694-3802

Fax: 1-204-694-3804

VANCOUVER

3179 Thunderbird Cres. Burnaby, BC V5A 3G1

Tel: 1-604-421-3096

Fax: 1-604-357-1112

The Hillman Group Canada, ULC

HILLMAN™