

versatile™ 4C Depot, DEP16S






NOTES:

Shown with 4C for dimensional reference only.

- 1. Depot cabinet design ensures compliance with USPS STD-4C mailbox installation regulations.
- 2. Accommodates all 4C front-loading single-column 16-High modules.
- 3. Depot cabinet assembled complete in factory.
- 4. Depot ships complete with 4C front-loading module installed.
- 5. May be installed outside or inside see foundation specification details in installation manual.



versatile™ 4C Mailbox, 4C16S-3P 17" R.O. → DEPTH → 17½" ACTUAL |-16¼" R.O. ູ່⊜ູ່ 561/2" 631/2" 55%16" R.O. ACTÚAL (TO PARCEL LOCK) 15" $14\frac{1}{8}$ " FROM FINISHED FLOOR (TO BOTTOM SHELF) TO BOTTOM OF R.O. FINISHED FLOOR

COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
PARCEL LOCKER	PL15	15" H x 12" W x 15" D	1
PARCEL LOCKER	PL5	17" H x 12" W x 15" D	1
PARCEL LOCKER	PL6	20-1/2" H x 12" W x 15" D	1

Notes:

- 1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox can also be used for private applications.
- 3. The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) $1\frac{1}{8}$ ".

PRODUCT SERIES: VERSATILETM 4C FRONT LOAD MAILBOX



5935 Corporate Drive • Manhattan, KS 66503 800 275 1747 • www florencemailboxes com

MODEL	4C16S-3P	REV	С
SCALE	NONE	LAS	T REV DATE 2/23/17
DRAWIN	G NUMBER		DRAWN BY
40	C16S-3PCS		NBC