


versatile™ 4C Depot, DEP16D






NOTES:

- 1. Depot cabinet design ensures compliance with USPS STD-4C mailbox installation regulations.
- 2. Accommodates all 4C front-loading double-column 16-High modules.
- 3. Depot cabinet assembled complete in factory.
- 4. Depot ships complete with 4C front-loading module installed.
- 5. May be installed outside or inside see foundation specification details in installation manual.



versatile™ 4C Mailbox, 4C16D-15



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.			
MAILBOX	MB1	3" H x 12" W x 15" D	15			
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1			
PARCEL LOCKER	PL15	15" H x 12" W x 15" D	2			
PARCEL LOCKER	PL5	17" H x 12" W x 15" D	1			

Notes:

- 1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox can also be used for private applications.
- 3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

PRODUCT SERIES: VERSATILETM 4C FRONT LOAD MAILBOX



5935 Corporate Drive • Manhattan, KS 66503 800 275 1747 • www florencemailboxes com

	MODEL 40	C16D-15	REV	
Ī	SCALE	NONE	LAS	t rev date 10/15/20
ſ	DRAWING	NUMBER		DRAWN BY
	4C	16D-15CS		NBC
	70	100 1000		1100