


# versatile™ 4C Mailbox, 4C16D-19



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB1	3" H x 12" W x 15" D	19
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1
PARCEL LOCKER	PL15	15" H x 12" W x 15" D	2

- Notes:**
1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
    - a. At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
    - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
    - c. No patron (tenant) lock shall be positioned more than 67" AFF.
    - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
    - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
  2. This 4C mailbox can also be used for private applications.
  3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator: [www.florencemailboxes.com/configurator](http://www.florencemailboxes.com/configurator).

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

<p style="font-size: small; margin-top: 5px;">5935 Corporate Drive • Manhattan, KS 66503 800 275-1747 • <a href="http://www.florencemailboxes.com">www.florencemailboxes.com</a></p>	MODEL 4C16D-19	REV F
	SCALE NONE	LAST REV DATE 4/17/26
	DRAWING NUMBER 4C16D-19CS	DRAWN BY RAK