



versatile™ 4C Mailbox, 13 High Suite



Floor



Floor

Notes:

1. Below are the USPS STD-4C installation guidelines:
 - a. At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
2. Modules noted with * do not meet USPS STD-4C guidelines above..
3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator:
www.florencemailboxes.com/configurator.

PRODUCT SERIES: versatile™ 4C Mailbox 13 High Suite

FLORENCE
CORPORATION
 5935 Corporate Drive • Manhattan, KS 66503
 800.275.1747 • www.florencemailboxes.com

MODEL	4C13H	REV	B
SCALE	NONE	LAST REV DATE	08/08/2019
DRAWING NUMBER	4C13HCS	DRAWN BY	RAK
		SHEET	1 OF 1