


versatile™ 4C Mailbox, 4C15D-13



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB2	6-1/2" H x 12" W x 15" D	11
MAILBOX	MB3	10" H x 12" W x 15" D	2
OUTGOING MAIL	OM1	3" H x 12" W x 15" D	1

- Notes:**
- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - No patron (tenant) lock shall be positioned more than 67" AFF.
 - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - The USPS Arrow lock shall be positioned 36"- 48" AFF.
 - This 4C mailbox can also be used for private applications.
 - The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

FLORENCE
CORPORATION
 5935 Corporate Drive - Manhattan, KS 66503
 800.275.1747 • www.florencemailboxes.com

MODEL	4C15D-13	REV	D
SCALE	NONE	LAST REV DATE	4/16/26
DRAWING NUMBER	4C15D-13CS	DRAWN BY	RAK