


versatile™ 4C Mailbox, 4C16S-04




COMPARTMENT CHART

| DESCRIPTION | COMPARTMENT | COMPARTMENT SIZE | QTY. |
|---------------|-------------|--------------------------|------|
| MAILBOX | MB2 | 6-1/2" H x 12" W x 15" D | 3 |
| MAILBOX | MB3 | 10" H x 12" W x 15" D | 1 |
| OUTGOING MAIL | OM1 | 3" H x 12" W x 15" D | 1 |
| PARCEL LOCKER | PL15 | 15" H x 12" W x 15" D | 1 |

Notes:

- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - No patron (tenant) lock shall be positioned more than 67" AFF.
 - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - The USPS Arrow lock shall be positioned 36"- 48" AFF.
- This 4C mailbox can also be used for private applications.
- The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

| | | |
|---|---------------------------|-----------------------|
| PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX | | |
|  <p>5935 Corporate Drive • Manhattan, KS 66503 800 275 1747 • www.florencemailboxes.com</p> | MODEL 4C16S-04 | REV E |
| | SCALE NONE | LAST REV DATE 4/17/26 |
| | DRAWING NUMBER 4C16S-04CS | DRAWN BY RAK |